

STANDARD SPECIFICATIONS and STANDARD DETAILS

OCTOBER 2013



CITY OF
Tulsa
A New Kind of Energy™

**CITY OF TULSA
ENGINEERING SERVICES DEPARTMENT
PAUL D. ZACHARY, DIRECTOR
2317 S. JACKSON AVE.
TULSA, OKLAHOMA 74107
(918) 596-9565**

TABLE OF CONTENTS
SPECIFICATIONS SECTIONS

DIVISION I – GENERAL SPECIFICATIONS

<u>PART</u>		<u>PAGE NO.</u>
101	Scope and Location	1
102	Scope, Nature, and Intent of Specifications and Drawings	1
103	Lines and Grades	2
104	Saturday, Sunday, Holiday and Night Work.....	2
105	Protection of Property	2
106	Connections.....	4
107	References to Other Specifications	4
108	Protection of Materials	5
109	Testing	5
110	“Or Approved Equal” Clause.....	6
111	Dewatering.....	6
112	Safety.....	6
113	Removal of Condemned Materials and Structures	8
114	Removal and Salvage of Castings.....	8
115	Clean-Up.....	8
116	Placing Work In Service.....	8
117	Submittals	9

DIVISION II – MATERIAL SPECIFICATIONS

<u>PART</u>		<u>PAGE NO.</u>
	Approved Fittings Manufacturers	1
201	Concrete	3
202	Quick-Setting Flowable Fill	12
203	Ductile Iron Pipe, Ductile and Cast Iron Fittings, and Valves	13
204	Steel Pipe and Fittings	21
205	Reinforced Concrete Pipe and Fittings	25
206	Vitrified Clay Pipe and Fittings	28
207	Polyvinyl Chloride (PVC) Pipe, Water Service	29
208	Polyvinyl Chloride (PVC) Pipe, Sewer Service	29
209	Castings.....	30
210	Conduit	31
211	Vaults, Pits and Manholes	32
212	Sand for Cushion or Backfill.....	37
213	Crushed Stone for Surfacing, Base Course, And Stabilization ...	37
214	Rip Rap.....	38

TABLE OF CONTENTS
SPECIFICATIONS SECTIONS

DIVISION III – CONSTRUCTION SPECIFICATIONS

<u>PART</u>		<u>PAGE NO.</u>
301	Right-Of-Way Clearing and Restoring.....	1
302	Excavation and Backfill, Unclassified.....	1
303	Mobilization/Demobilization	4
304	Contractor Construction Staking	4
305	Pipe, Vitrified Clay	5
306	Pipe, Reinforced Concrete.....	6
307	Pipe, Ductile Iron	7
308	Pipe, Steel	8
309	Polyvinyl Chloride (PVC) Pipe, Water Service	9
310	Locator Wire and Detectable Marking Tape.....	10
311	Tapping of PVC Pipe for Service Connections	10
312	Fittings	10
313	Polyvinyl Chloride (PVC) Pipe, Sewer Service	11
314	Manhole.....	12
315	Connection.....	14
316	Lamphole	16
317	Valve.....	16
318	Valve Box.....	17
319	Encasement, Concrete	17
320	Cradle, Concrete.....	18
321	Piers, Reinforced Concrete.....	18
322	Conduit, Bored.....	18
323	Structure, Special	19
324	Materials Furnished By Contractor and Installed By City	19
325	Sodding and Seeding	19
326	Street Wash Down.....	20
327	Traffic Control Devices.....	20
328	Bore	21
329	Pavement, Removal and Replacement	21
330	Erosion Control Measures	23
331	Water Table Cradle.....	23
332	Conduit, Open Cut	24

TABLE OF CONTENTS
SPECIFICATIONS SECTIONS

DIVISION IV – SANITARY SEWER REHAB CONSTRUCTION SPECIFICATIONS

<u>PART</u>		<u>PAGE NO.</u>
400	General Provision	1
401	Site Preparation	7
402	Restoration	10
403	Backfill	18
404	Removal, Salvage, and Abandonment of Existing Facilities	21
405	Pipeline and Installation	22
406	Pipe Reaming	25
407	Pipe Crushing	30
408	Pipe Bursting	35
409	Sliplining	41
410	Cured-in-Place Pipe.....	51
411	Pipeline Pressure Grouting	60
412	Point Repairs	66
413	Concrete Embankment	68
414	Clay Dam.....	70
415	Construction Television Inspection of Sanitary Sewer	71
416	Complete Manhole Replacement.....	73
417	Replacement of Cleanout / Lamphole and/or Cleanout / Lamphole Frame and Cover	77
418	Replacement of Manhole Frame and Cover, Frame Seal, Chimney, and Grade Adjustment	79
419	Patching, Repairs, and Plugging Lift Holes.....	87
420	Manhole Step Removal and Replacement.....	89
421	Interior Manhole Rehabilitation – Corbel (Cone) and Wall Rehabilitation, Bench and Invert and Pipe Seal Rehabilitation ...	91
422	Manhole Testing of New and Rehabilitated Manholes.....	101
423	Obstruction Removal	103
424	Cured-in-Place Sectional and Spot Repair	104
425	Oversized Manhole Frame and Cover	109
426	Sealed Manhole Frame and Cover	111

TABLE OF CONTENTS
SPECIFICATIONS SECTIONS

DIVISION V – WATER METER SPECIFICATIONS

<u>PART</u>		<u>PAGE NO.</u>
	Approved Meter and Back Flow Preventer Manufacturers.....	1
500	Definitions	2
501	Displacement Water Meters – 5/8” x 3/4”, 1”, & 1-1/2”	3
502	Compound Type Water Meters – 2”, 3”, 4”, 6”, & 8”	6
503	Turbine Water Meters – Irrigation and Special Services – 2” & 3”	9
504	Turbine Meters – Fire Service – 4”, 6”, 8”, & 10”	12
505	Fire Flow Meters – 4”, 6”, 8”, & 10”	15
506	Double Check Detector Assembly– 4”, 6”, 8”, & 10”	17

DIVISION VI – TRAFFIC SPECIFICATIONS – MATERIALS

<u>PART</u>		<u>PAGE NO.</u>
601	Pull Boxes.....	1
602	Electrical Conduit.....	3
603	Signal Pole Footings.....	8
604	Loop Detectors	10
605	Blank (Reserved for future use)	
606	Pre-Emption and Signal Priority Systems	15
607	Power Supplies.....	17
608	Traffic Signs.....	20
609	Pavement Markings (Reserved for future use)	
610	Traffic Signal Controller Cabinet Assembly.....	22
611	Electrical Conductors Traffic Signal	30
612	Cabinet Bases, Aprons, and Guards	34
613	Pedestrian Push Button	36
614	LED Traffic Signal Heads and Pedestrian Signal Heads	37
615	Base Covers	41
616	Mast Arm Brackets	42
617	Signal Poles and Mast Arms.....	42
618	Bonding.....	45
619	Temporary Signals.....	46
620	Video Detection System.....	48
621	Highway, Street and Pedestrian Lighting.....	49
622	Wireless Traffic Signal Communications System.....	53
623	Battery Backup	54
624	Remove and Reset Existing Traffic Signal Controller Assembly.....	56
625	Removal of Traffic Items	57
626	Traffic Signal Construction and Operation	58
627	Pre-Qualification for Traffic Operations Materials	61
628	Signal and Lighting Project Contractor Experience Requirements	65

TABLE OF CONTENTS
SPECIFICATIONS SECTIONS

DIVISION VII – ORDINANCE 22597

Adoption of ODOT “Standard Specifications for Highway Construction” 2009 Edition, by City of Tulsa.

STANDARD DETAILS INDEX
(found in small book)

101	Fire Proof Area
102	Project Sign
103	Guidelines for Blasting Sign
301	Dual 3/4” Long Service From 1” Feed
302	Conduit for Future Service Lines
303	Dual Domestic/Sprinkler From 2” Line
304	Bedding Detail – Rigid Pipe
305	Bedding Detail – Semi Rigid Pipe
306	Trench Detail Construction Adjacent to Roadway
307	Bore/Open Cut Conduit Detail
308	Combination Air Vacuum / Air Relief, Check Valves, and Vaults
309	Fire Hydrant
310	Blowoff Hydrant
311	Sampling Tap on 4” – 12” Water Lines
312	Frame and Lid for Water Vaults
313	Valve Box
314	Manhole Steps
315	Thrust Blocks and Trench Conditions
351	Bedding Detail PVC Flexible Sanitary Sewer Pipe
352	Frame and Lid for Manholes
353	Frame and Lid for 4’ I.D. Sanitary Manhole
354	Frame and Lid for 5’ I.D. and Larger Sanitary Manhole
355	Brick Manhole (Special Approval Only)
356	Sanitary Sewer Manhole with Taper
357	Sanitary Sewer Manhole with Flat Slab Top
358	Sanitary Sewer Pre-Cast Sanitary Sewer Manholes
359	Not Used
360	Frame and Lid for Lampholes
361	In-Line Tees for Service Connection
362	Riser Detail
363	Riser Detail with Sloped Trench
364	Sanitary Sewer Combination Air Relief Valve Installation
365	Go, No-Go Deflection Testing Mandrel
366	Manhole Step Location and Invert Details
367	Water Table Cradle
401	Manhole Grade Adjustment
401A	Concrete Collar for Partial Manhole Replacement
402	Cover, Frame and Frame Seal Repair

STANDARD DETAILS INDEX
(found in small book)

403	Special Detail for Interior Coating System
404	Step Removal
405	Rubber Seal At Manhole
406	Shallow Flattop Manhole
407	Bench and Invert Rehabilitation
408	Excavation and Restoration At Grade And Above Grade Construction
409	Concrete Manhole Collar
410	Corbel (Cone) Replacement
411	Chemical Pressure Grouting - Precast Manhole
412	Chemical Pressure Grouting - Brick Manhole
413	Patch Hole and Plug Lift Hole
414	Manhole Adjusting Ring
415	Clay Dam
501	Standard Meter Settings for 5/8" x 3/4" and 3/4" Water Service
502	Standard Meter Settings for 1" Water Service
503	Standard Meter Settings for 1-1/2" Water Service
504	Standard Meter Settings for 2" Water Service
505	Meter Can with Rim and Lid 5/8" x 3/4" and 1" Water Meter Can Installation
506	Meter Can with Rim and Lid 1-1/2" Water Meter Installation
507	Meter Can with Rim and Lid 2" Water Meter Installation
508	Offset Plug
701	Residential Concrete Driveway Concrete Street
702	Residential Concrete Driveway Asphalt Street
703	Residential Asphalt Driveway Concrete Street
704	Residential Asphalt Driveway Asphalt Street
705	Temporary Residential Driveway (No Curb)
706	Commercial Driveway
707	Commercial Driveway
708	Commercial Asphalt Driveway
709	Parking Lots
710	Temporary Commercial Driveway (No Curb)
711	Not Used
712	Not Used
713	Pavement Removal and Replacement
714	Pavement Cuts
715	HWY-PVT-RPL for State Highways that are Arterial Streets
751	Pipe Bedding Detail for Storm Sewer
752	Frame and Lid for Stormwater Manholes
753	Frame and Lid for 4' and 5' I.D. Stormwater Manhole
754	Frame and Lid for 6' and 8' I.D. Stormwater Manhole and Junction Boxes
755	Configurations of Cast Iron Curb Inlets
756	Private Storm Sewer Connected to Public Storm Sewer
757	Public or Private Storm Sewer Connected to Public Storm Sewer
758	Residential Storm Water Curb Opening

STANDARD DRAWINGS INDEX
(found in large book)

126	Standard Straw Bale Dike, Silt Fence, and Construction Entrance
325	Ball Valve Vault Std For 16" & 24" Lines Under H-20 Loading
326	Ball Valve Vault Std For 30" thru 48" Line Under H-20 Loading
327	Combination Air Vacuum/Relief Valve Vault for 2" ARV Less Than 5 lbs. In Weight
328	Standard 4" 6" 8" Air Valve Assembly On 16" thru 48" Main
329	Standard 8" and 12" Blowoff Assembly
330	Cathodic Protection
331	Details for 6' – 8' Sanitary Sewer Manholes
525	3" Meter Standard and Vault Assembly
526	3" Meter with Pressure Sustaining Valve Assembly and Vault
527	4" Meter Assembly and Vault
528	4" Meter with Pressure Sustaining Valve Assembly and Vault
529	6" Meter Standard and Vault Assembly
530	6" Meter with Pressure Sustaining Valve Assembly and Vault
531	8" Meter Standard and Vault Assembly
532	8" Meter with Pressure Sustaining Valve Assembly and Vault
533	10" Meter Standard and Vault Assembly
534	10" Meter with Pressure Sustaining Valve Assembly and Vault
535	NOT USED
536	NOT USED
537	NOT USED
550	Backflow Prevention Options Index
551	4", 6", 8" Detector Check Assembly and Meter Can
552	4" - 10" Detector Check Assembly and Vault
553	4" - 10" Double Check Detector and Vault Assembly
601	Pull Box Installation
602	Conduit Installation
603	Signal Pole Footing Details
604A	Installation of Detectors
604B	Detector Wire Installation
605	NOT USED
606	Emergency Pre-emption Detail
607A	Traffic Signal Service Pole and Service to Signal Standard
607B	Traffic Signal Pedestal Service
608A	Street Name Signs
608B	Traffic Signs
609	NOT USED
610A	332 Controller Cabinet Detail
610B	336S Controller Cabinet Detail
610C	332 Cabinet Wiring
611A	Pole Wiring Detail
611B	Downtown Pedestal Wiring Detail
612	Cabinet Guard Detail
613	Pedestal and Mast Arm Pole Details
614A	Traffic Signals and Accessories

STANDARD DRAWINGS INDEX
(found in large book)

614B	Signal Head Wiring
615	NOT USED
616	Mast Arm Brackets
617A	Signal Poles and Mast Arms
617B	Single Mast Arm Details
618	Bonding Diagram
619	NOT USED
620	NOT USED
621A	Lighting Controller Details
621B	Lighting Wiring Details
725	Standard Pavement Patch and Repair
726	Asphalt Pavement Standard Details for Residential and Collector Streets
727	Concrete Pavement Standard Details for Residential and Collector Streets (1 of 2)
728	NOT USED
729	Concrete Pavement Standard Details for Residential and Collector Streets (2 of 2)
730	Standard Asphalt Pavement Cut and Repair
731	Standard Concrete Pavement Cut and Repair
732	All-Weather Parking Surfaces for Light Duty Residential Parking
733	Standard Pavement Rehabilitation for Utility Construction
761	Standard Inlets and Grates w/ Access Manhole Back of Curb
762	Precast Standard Inlets and Grates w/Access Manhole Back of Curb
763	Standard Masonry Stormwater Inlets (for rehabilitation and reference only)
764	Standard Reinforced Concrete Stormwater Inlets
765	Standard Stormwater Frames
766	Standard Stormwater Grates
767	Standard Cast Iron Curb
768	Standard Recessed Curb Inlet
769	NOT USED
770	Standard Drop Inlet 15", 18", and 24"
771	Standard Drop Inlet 30", 36", and 42" with no Access Manhole
772	Standard Drop Inlet 48" Pipe
773	Standard Three Way Drop Inlet 48" Pipe
774	Standard Masonry Manhole and Junction Box (for rehabilitation and reference only)
775	Standard Precast Concrete Stormwater Manhole
776	Standard Pipe Headwalls 15" to 42"
777	NOT USED
778	Grouted RipRap Protection for Existing Headwall (for reference only)
779	Standard Energy Dissipator
780	Standard Baffle Block Energy Dissipator
781A-D	Semi-Elliptical Storm Sewer
782	Standard Low-Flow Concrete Channel Typical Layout
783	Concrete Lined Channel
784	Vertical Wall Channel
785	Standard Dikes and Swales
786	NOT USED

STANDARD DRAWINGS INDEX
(found in large book)

787	Sidewalk Grate for Tree Well
788	Single Pole Gate
789	Double Pole Gate
790	Standard Sidewalk Ramp
791	Special Type I Drop Inlet
792	Special Type II Drop Inlet