



TRENCH CROSS-SECTION

NOTE:

1. BEDDING SHALL BE SAND, PLACED IN THE TRENCH SIMULTANEOUSLY ON BOTH SIDES OF THE PIPE, AND HAND TAMPED TO ASSURE CONSOLIDATION.
2. FOR PAVED AREAS, SEE STANDARD DETAIL FOR PAVEMENT REMOVAL AND REPLACEMENT.
3. CONTRACTOR SHALL BEAR ALL COSTS OF TESTING.
4. COMPACTION SHALL BE 95% STANDARD PROCTOR DENSITY PER AASHTO T-99 IN 8" LIFTS.

RIGID PIPE:

1. DUCTILE IRON - AWWA C151
2. PRESTRESSED CONCRETE - AWWA C301
3. REINFORCED CONCRETE SANITARY SEWER
4. VITRIFIED CLAY SANITARY SEWER

BEDDING DETAIL RIGID PIPE	
CITY OF TULSA, OKLAHOMA ENGINEERING SERVICES DEPARTMENT	
DRAWN BY: R.M.O.	APPROVED: 
CHECKED BY: 	
DATE: FEBRUARY 2017	
NOT TO SCALE	STANDARD NO. 304