1 1/2" ALUMINUM CAP-FLUSH-SET IN CONCRETE- STAMPED "64", SET N.E. OF THE INTERSECTION OF APACHE ST, AND UTICA AVE. ELEVATION = 651.72' (NAVD 1988) N = 440109.581 / E = 2568295.152

BENCHMARK #65 (COT ADS NETWORK)

1 1/2" ALUMINUM CAP-FLUSH-SET IN CONCRETE- STAMPED "65", SET ON THE NORTH SIDE OF 36TH ST N AND APPROX. 0.40 MILES WEST OF LEWIS AVE. ELEVATION = 629.22' (NAVD 1988) N = 445332.998 / E = 2568694.122

SURVEY CONTROL DATA

HORIZONTAL CONTROL

A. OKLAHOMA STATE PLANE COORDINATE SYSTEM, LAMBERT PROJECTION, NORTH ZONE. (NAD83)

B. ACCURACY - 3RD ORDER OR BETTER.

BEARINGS

THE BEARINGS SHOWN HEREIN ARE GRID BEARINGS DERIVED FROM THE OKLAHOMA STATE PLANE COORDINATE SYSTEM AND ARE NOT ASTRONOMICAL.

VERTICAL CONTROL

A. LEVEL DATUM IS NAVD 1988

B. ACCURACY - 3RD ORDER OR BETTER.

CONSTRUCTION PLANS FOR WILSHIRE TRAILS SANITARY SEWER IMPROVEMENTS PROJECT NO. ES 2023-19 WATER & SEWER DEPARTMENT CITY OF TULSA, OKLAHOMA

PROJECT LOCATION 3200 North Madison Avenue

SYMBOL LEGEND

1	CPED	CABLE / TV / DATA BOX
E	EM	ELECTRIC METER
	EPED	ELECTRIC BOX
EMP	XFMR	ELECTRIC TRANSFORME
0	FH	FIRE HYDRANT
0	FP	FLAGPOLE
-©-	GM	GAS METER
•	GV	GAS VALVE
\circ	GUY	GUY ANCHOR
	ICV	IRRIGATION CONTROL V
-×-	LP	LIGHT POLE
	MB	MAILBOX
-	PP	POWER POLE

O TS TRAFFIC SIGN O SSCO SANITARY SEWER CLEANOUT

STORM WATER MANHOLE TELEPHONE PEDESTAL

WATER VALVE

BM-4

DECIDUOUS TREE (ALL TYPES) CONIFEROUS TREE (ALL TYPES) FENCE LINE (ALL TYPES) STORM SEWER SANITARY SEWER OVERHEAD ELECTRIC OVERHEAD TELEPHONE NATURAL GAS LINE UNDERGROUND TELEPHONE UNDERGROUND ELECTRIC UNDERGROUND CABLE EXISTING MINOR CONTOUR


BORE LOCATION

SITE BENCHMARK

UTILITY COORDINATION INFORMATION TULSA ENGINEERING SERVICES DEPARTMENT WATER DESIGN 596-9564 WASTEWATER DESIGN 596-9636 TRANSPORTATION DESIGN 596-9741 TRAFFIC ENGINEERING DESIGN 596-9498 STORMWATER DESIGN COT UTILITY COORDINATION 596-9649 OKLAHOMA NATURAL GAS CO. 831-8215 COX COMMUNICATIONS 286-4716 250-6257 AEP\PSO 596-4237 MTTA 830-0024

PLANS PREPARED BY

Engineered By Design, PLLC P.O. Box 15567, Del City, Oklahoma 73155 Phone: 405.234.0980 / Email: ahale@engineeredbydesign.pro CA#7655 / Exp. Date 6.30.2024



65TH W AVE
49TH W AVE
33RD W AVE
UNION AVE
ELWOOD AVE
IEWOOD AVE
IARVARD AVE
VALE AVE
SHERIDAN RD
IEMORIAL DR
IEMORIAL DR
129TH E AVE
145TH E AVE



Index to Drawings

COVER SHEET
SANITARY SEWER QUANTITIES & NOTES
STORMWATER MANAGEMENT PLAN
SANITARY SEWER PLAN
SANITARY SEWER PROFILES
SANITARY SEWER PROFILES & DETAILS

City of Tulsa Standards

102	PROJECT SIGN	

BEDDING DETAIL FOR RIGID PIPE

TRENCH DETAIL FOR CONSTRUCTION ADJACENT TO A ROADWAY

BEDDING DETAIL PVC FLEXIBLE SANITARY SEWER PIPE FRAME AND LID FOR MANHOLES

FRAME AND LID FOR 4' ID SANITARY SEWER MANHOLES

SANITARY SEWER PRE-CAST MANHOLES IN-LINE TEES FOR SERVICE CONNECTION

363 RISER DETAIL

366 MANHOLE STEP LOCATION AND INVERT DETAILS



APPROVED BY



WATER AND SEWER DIRECTOR

DATE

AARON S. HALE, P.E.

ENGINEERED BY DESIGN, PLLC

March 11, 2024 DATE

9.9.2025

August 19, 2025 **REVISION #6**



STORMWATER MANAGEMENT PLAN

Soil Stablization Practices: Site Description: PROJECT LIMITS: THIS PROJECT IS A TMUA SANITARY SEWER IMPROVEMENT PROJECT: TEMPORARY SEEDING EAST 32ND PLACE NORTH WEST TO STREET DEAD END X PERMANENT SODDING EAST 32ND STREET NORTH EAST TO NORTH MADISON AVENUE MULCHING SOIL RETENTION BLANKET X PRESERVATION OF EXISTING VEGETATION OTHER: PROJECT DESCRIPTION: SANITARY SEWER EXTENSION SUGGESTED SEQUENCE OF CONSTRUCTION: INSTALL TEMPORARY EROSION CONTROL DEVICES INSTALL NEW SANITARY SEWER AS NECESSARY Structural Practices: SITE CLEANUP AND STABILIZATION REMOVE TEMPORARY EROSION CONTROLS X SILTATION SCREENS X SILT DIKE AND SILT FENCE DIVERSION, INTERCEPTOR OR PERIMETER DIKES DIVERSION, INTERCEPTOR OR PERIMETER DITCHES DIVERSION DIKE AND DITCH COMBINATIONS PIPE SLOPE DRAINS TOTAL AREA TO BE DISTURBED: APPROXIMATELY 0.4 ACRES ± PAVED DITCH AND DITCH LINER PROTECTION NOTE: THIS AREA IS TO BE CALCULATED AS "R/W TO R/W" FOR THE EXTENTS OF THE PROJECT. INCLUDING ANY INCIDENTAL CONSTRUCTION. ENERGY DISSIPATING DEVICES (INLETS WITH VANE GRATES SHALL BE USED AS VELOCITY DISSIPATION DEVICES) TEMPORARY SEDIMENT BASINS WEIGHTED RUNOFF COEFFICIENT: 0.65 (RESIDENTIAL) TEMPORARY SEDIMENT FILTERS (CONTRACTOR SHALL USE NOTE: THIS SHOULD BE DETERMINED BY THE HYDRAULIC DESIGNER FOR THE PROJECT. THIS DANDY BAGS ON ALL INLETS THROUGHOUT CONSTRUCTION -VALUE SHOULD BE THE AVERAGE "C" FACTOR USED ON THE PROJECT. IT SHOULD BE BASED COST TO BE INCLUDED IN OTHER ITEMS OF WORK) ON ANTICIPATED FUTURE LAND USE. NAME OF RECEIVING WATERS: UNNAMED TRIBUTARY TO DIRTY BUTTER CREEK Offsite Vehicle Tracking: NOTE: THIS SHOULD DESCRIBE EACH NAMED CREEK, RIVER, OR BODY OF WATER WHICH IS RECEIVING STORM WATER RUNOFF. HAUL ROADS DAMPENED FOR DUST CONTROL X LOADED HAUL TRUCKS TO BE COVERED WITH TARPAULIN NOTE: THIS SHEET SHOULD BE USED IN CONJUNCTION WITH A DRAINAGE OR SITE MAP THAT X EXCESS DIRT ON ROAD REMOVED DAILY ILLUSTRATES THE DRAINAGE CHARACTERISTICS AND RECEIVING WATERS FOR THE PROJECT. STABILIZED CONSTRUCTION ENTRANCE/EXIT ENDANGERED SPECIES: THIS PROJECT IS NOT LOCATED WITHIN THE FEDERAL OR STATE LISTED SENSITIVE AREAS. THIS PROJECT IS NOT LIKELY TO SIGNIFICANTLY EFFECT ENDANGERED OR THREATENED SPECIES. NO FURTHER INVESTIGATION IS NECESSARY FOR THIS SITE. Additional Information: STAGING AREA IS CONTRACTOR DEPENDENT AND NOT SHOWN - CONTRACTOR SHALL SUPPLY A STAGING AND WORKFLOW SCHEDULE TO THE CITY OF TULSA PRIOR TO WORK AND IT SHALL BECOME PART OF THE SWP3. KEEPING PLANS CURRENT: AS PER PART IV SECTION E.2.d.2 OF THE OPDES PERMIT OKR10 LANGUAGE (SEE CONTRACT DOCUMENTS) THE OWNER/OPERATOR OF THIS PROJECT AGREES TO UPDATE THIS STORM SEWER POLLUTION PREVENTION PLAN . . . TO REMAIN CONSISTENT WITH ANY CHANGES APPLICABLE TO PROTECTING SURFACE WATER RESOURCES IN SEDIMENT EROSION SITE PLANS OR SITE PERMITS, OR STORM WATER MANAGEMENT SITE PLANS OR SITE PERMITS APPROVED BY STATE OR LOCAL OFFICIALS FOR WHICH THE PERMITTEE RECEIVES WRITTEN NOTICE.

Other Erosion and Sediment Controls:

THE CONTRACTOR SHALL ALSO BE RESPONSIBLE FOR THE FOLLOWING:

MAINTENANCE AND INSPECTION:

ALL EROSION AND SEDIMENT CONTROLS WILL BE MAINTAINED IN GOOD WORKING ORDER FROM THE BEGINNING OF CONSTRUCTION UNTIL AN ACCEPTABLE VEGETATIVE COVER IS ESTABLISHED. INSPECTION BY THE CONTRACTOR AND ANY NECESSARY REPAIRS SHALL BE PERFORMED ONCE EVERY 7 CALENDAR DAYS AND WITHIN 24 HOURS AFTER ANY STORM EVENT GREATER THAN 0.5 INCH (AS RECORDED BY A NON-FREEZING RAIN GAUGE TO BE LOCATED ON-SITE). POTENTIALLY ERODIBLE AREAS, DRAINAGEWAYS, MATERIAL STORAGE, STRUCTURAL DEVICES, CONSTRUCTION ENTRANCES AND EXITS ALONG WITH EROSION AND SEDIMENT CONTROL LOCATIONS ARE EXAMPLES OF SITES THAT NEED TO BE INSPECTED.

WASTE MATERIALS:

PROPER MANAGEMENT AND DISPOSAL OF CONSTRUCTION WASTE MATERIAL IS REQUIRED BY THE CONTRACTOR. MATERIALS INCLUDE STOCKPILES, SURPLUS, DEBRIS AND ALL OTHER BY-PRODUCTS FROM THE CONSTRUCTION PROCESS. PRACTICES INCLUDE DISPOSAL, PROPER MATERIALS HANDLING, SPILL PREVENTION AND CLEANUP MEASURES. CONTROLS AND PRACTICES SHALL MEET THE REQUIREMENTS OF ALL FEDERAL, STATE AND LOCAL AGENCIES.

HAZARDOUS WASTE:


PROPER MANAGEMENT AND DISPOSAL OF HAZARDOUS WASTE MATERIAL IS REQUIRED THE CONTRACTOR IS RESPONSIBLE FOR FOLLOWING MANUFACTURER'S RECOMMENDATIONS, STATE AND FEDERAL REGULATIONS TO ENSURE CORRECT HANDLING, DISPOSAL, SPILL PREVENTION AND CLEANUP MEASURES. EXAMPLES INCLUDE BUT ARE NOT LIMITED TO: PAINTS, ACIDS, CLEANING SOLVENTS, CHEMICAL ADDITIVES, CONCRETE CURING COMPOUNDS AND CONTAMINATED SOILS.


GENERAL NOTES:

A STORM WATER POLLUTION PREVENTION PLAN (SWP3) IS REQUIRED TO COMPLY WITH THE OKLAHOMA POLLUTION DISCHARGE ELIMINATION SYSTEM (OPDES GENERAL PERMIT OKR-10) REGULATIONS. THIS PLAN IS DEVELOPED DURING THE DESIGN PHASE, CONFIRMED IN THE PRE-WORK MEETINGS AND AVAILABLE ON THE JOB SITE. THE BASIC GOAL OF STORM WATER MANAGEMENT IS TO IMPROVE WATER QUALITY BY REDUCING POLLUTANTS IN STORM WATER DISCHARGES. RUNOFF FROM CONSTRUCTION SITES HAS A POTENTIAL FOR POLLUTION DUE TO EXPOSED SOILS AND THE PRESENCE OF HAZARDOUS MATERIALS USED IN THE CONSTRUCTION PROCESS. THE PREVENTION OF SOIL EROSION, CONTAINMENT OF HAZARDOUS MATERIALS AND/OR THE INTERCEPTION OF THESE POLLUTANTS BEFORE LEAVING THE CONSTRUCTION SITE ARE THE BEST PRACTICES FOR CONTROLLING STORM WATER POLLUTION.

THE FOLLOWING SUBSECTIONS OF THE 2019 ODOT STANDARD SPECIFICATIONS SHOULD BE NOTED:

SECTION 220 - TEMPORARY EROSION, SEDIMENTATION, AND STORMWATER POLLUTION PREVENTION AND CONTROL





EXISTING UNDERGROUND LINES HAVE BEEN SHOWN TO

ALL CONSTRUCTION TO BE IN STRICT ACCORDANCE

EDITION AND APPLICABLE SUPPLEMENTS.

ITY COMMENTS

STORMWATER MANAGEMENT PLAN PROJECT NO. TMUA-W 21-11

Wilshire Trails Waterline Replacement

Engineered By Design, PLLC

10700 Mycrs Lanc, Choctaw, OK 73020

CITY OF TULSA, OKLAHOMA
WATER AND SEWER DEPARTMENT

REVISION	BY	DATE	PLAN SCAL
REVISED BID ALTERNATES	SD	5/13/24	N/A
ADDED PAY ITEM	NATERLINE QUANTITIES SD 6/		
WATERLINE QUANTITIES	SD	6/26/24	PROFILE SO
CITY COMMENTS	SD	7/24/25	HORIZONTA
CITY COMMENTS	SD	7/28/25	N/A
CITY COMMENTS	SD	7/29/25	VERTICAL:
CITY COMMENTS	SD	7/31/25	N/A
CITY COMMENTS	SD	8/4/25	FILE:

WITH CURRENT CITY OF TULSA ENGINEERING PLANS AND STANDARD SPECIFICATIONS, INCLUDING O.D.O.T. 2019 ESTIMATE

LI AKED DI.	32		CA#7655 /	Exp. Date 6.30.202		
AN SCALE:	DRAWN	SD	03/2024	APPROVED		
N/A	DESIGNED	EBD	03/2024			
	SURVEY	LLS	02/2022			
OFILE SCALE	PROJ MGR.	9	09/2025			
RIZONTAL:	LEAD ENGR.	WIL	09/25			
N/A	FIELD MGR.	Then	9/25			
OTICAL:	RECOMMENDE	C)				

DRAWING:

PREPARED BY

SD 8/19/25 ATLAS PAGE NO: 218

FIGURE TO ATE:

DATE:
SHEET 3 OF 6 SHEETS

		SANITARY SEWER PAY QU	MITTIES		
SANITAR	Y SEWER BASE	BID			
ITEM	SPEC NO.	DESCRIPTION	PAY ITEM NOTE	UNIT	QUANTITY
1	COT 102	PROJECT SIGN		EA	1
2	COT 301	RIGHT-OF-WAY CLEARING AND RESTORING, COMPLETE IN PLACE	2	LF	463
3	COT 302	EXCAVATION & BACKFILL, UNCLASSIFIED		CY	284
4	COT 303	MOBILIZATION		EA	1
5	COT 304	CONSTRUCTION STAKING		EA	1
6	COT 309	INSTALL 8" PVC PIPE (SDR-26)	15	LF	463
7	COT 314	STANDARD 4' I.D. MANHOLE	6	EA	4
8	COT 314	VERTICAL FOOT, EXTRA DEPTH OVER 6' DEEP	6	VF	2
9	COT 334	CONSTRUCTION AS-BUILTS		LS	1
10	COT 335	CONTRACTOR'S QUALITY CONTROL		LS	1
11	COT 402	SODDING	5	SY	1,030
12	SPECIAL	OWNERS ALLOWANCE	18	ALLOWANCE	10,000
ADD ALT	ERNATE NO. 1				
13	COT 301	RIGHT-OF-WAY CLEARING AND RESTORING, COMPLETE IN PLACE	2	LF	105
14	COT 302	EXCAVATION & BACKFILL, UNCLASSIFIED		CY	64
15	COT 309	INSTALL 8" PVC PIPE (SDR-26)	15	LF	105
16	COT 314	STANDARD 4' I.D. MANHOLE	6	EA	1
17	COT 314	VERTICAL FOOT, EXTRA DEPTH OVER 6' DEEP	6	VF	0.8
18	COT 402	PAVEMENT REMOVAL AND REPLACEMENT - ASPHALT	2,3	SY	8
19	COT 402	SODDING	5	SY	235
20	COT 880	TRAFFIC CONTROL	9	CD	30
ADD ALT	ERNATE NO. 2				
21	COT 301	RIGHT-OF-WAY CLEARING AND RESTORING, COMPLETE IN PLACE	2	LF	71
22	COT 302	EXCAVATION & BACKFILL, UNCLASSIFIED		CY	45
23	COT 309	INSTALL 8" PVC PIPE (SDR-26)	15	LF	71
24	COT 314	STANDARD 4' I.D. MANHOLE	6	EA	1
25	COT 314	VERTICAL FOOT, EXTRA DEPTH OVER 6' DEEP	6	VF	1.2
26	COT 315	8"x4" IN-LINE TEE, PLUG AND RISER W/ TAPE		EA	2
27	COT 402	SODDING	5	SY	158
ADD ALTI	ERNATE NO. 3				
28	COT 301	RIGHT-OF-WAY CLEARING AND RESTORING, COMPLETE IN PLACE	2	LF	193
29	COT 302	EXCAVATION & BACKFILL, UNCLASSIFIED		CY	127
30	COT 309	INSTALL 8" PVC PIPE (SDR-26)	15	LF	193
31	COT 314	VERTICAL FOOT, EXTRA DEPTH OVER 6' DEEP	6	VF	1,1
32	COT 314	STANDARD 4' I.D. MANHOLE	6	EA	1
33	COT 402	PAVEMENT REMOVAL AND REPLACEMENT - ASPHALT	2,3	SY	8
34	COT 402	SODDING	5	SY	430
35	ODOT 880	TRAFFIC CONTROL	9	CD	30

Traffic Control

- 1. ALL TRAFFIC CONTROL DEVICES, CONSTRUCTION SIGNAGE, BARRICADING, ETC. SHALL BE IN ACCORDANCE WITH THE LATEST REVISED EDITION OF THE MANUAL ON UNIFORM TRAFFIC CONTROL DEVICES (MUTCD). CONTRACTOR SHALL PREPARE. AND SUBMIT FOR APPROVAL A TRAFFIC CONTROL PLAN
- 2. THE CONTRACTOR SHALL PROVIDE 48 HOUR NOTIFICATION FOR ANY AND ALL STREET 1 LANE CLOSURES, MODIFICATIONS, OR CHANGES TO THE TRAFFIC CONTROL MEASURES TO:

POLICE	918-569-9222
FIRE	918-596-9977
COT TRAFFIC	918-596-9744
EMSA	918-596-3043
MTTA	918-585-1195

- 3. THE CONTRACTOR SHALL NOTIFY TRAFFIC OPERATIONS 48 HOURS PRIOR TO STARTING WORK OR PRIOR TO REMOVING OR RELOCATING ANY TRAFFIC SIGNS. ALL SIGNS SHALL BE HANDLED SO AS TO AVOID ANY DAMAGE TO THE SIGN OR POST. ALL SIGNS REMOVED DUE TO CONSTRUCTION SHALL BE REINSTALLED BY THE CONTRACTOR.
- 4. THE CONTRACTOR SHALL BE RESPONSIBLE FOR THE MAINTENANCE OF ALL CONSTRUCTION SIGNAGE AND BARRICADING. INCLUDING, BUT NOT LIMITED TO, WASHING, REPLACEMENT, REPOSITIONING OF DEVICES. WHEN AND WHERE IT IS DEEMED NECESSARY BY THE CITY OR THE ENGINEER, THE CONTRACTOR SHALL FURNISH AND INSTALL ANY ADDITIONAL TRAFFIC CONTROL DEVICES.
- 5. LOCAL AND THROUGH TRAFFIC SHALL BE MAINTAINED THROUGH THE PROJECT AREA AT ALL TIMES. LOCAL TRAFFIC TO ALL PUBLIC AND PRIVATE STREETS SHALL BE ACCESSIBLE FROM ANY DETOURS DURING THE CONSTRUCTION OF THIS PROJECT.
- 6. ROADSIDE HAZARDS SHALL BE COMPLETELY BARRICADED AROUND THEIR PERIMETER FOR SAFETY OF PEDESTRIANS AND VEHICLES. NO BARRICADES SHALL BE PLACED UNTIL ALL ADVANCE SIGNING IS IN PLACE.
- 7. ALL CHANNELING DEVICES, TYPE III BARRICADES, ETC. SHALL BE WEIGHTED DOWN WITH NON-HAZARDOUS MATERIAL WHEN NECESSARY OR WHEN DIRECTED BY THE CITY OR THE ENGINEER.
- ALL ADVANCE SIGNS SHALL BE TYPE "A" WARNING LIGHTS.
- ALL TYPE III BARRICADES SHALL BE FURNISHED WITH A MINIMUM OF TWO (2) TYPE "A" WARNING LIGHTS.
- ALL CHANNELING DEVICES SHALL BE PROVIDED WITH TYPE "C" WARNING LIGHTS.

Sanitary Sewer Pay Item Notes

NOT USED.

2.1. ITEM INCLUDES THE COST FOR REMOVAL OF TREES AND SHRUBS WITHIN EASEMENTS AND REMOVING AND REPLACING EXISTING FENCE AND SIDEWALK IF DISTURBED BY CONSTRUCTION. NO ADDITIONAL PAYMENT WILL BE MADE.

2.2. CONTRACTOR SHALL BE RESPONSIBLE FOR TRENCH DEWATERING, NO SEPARATE PAYMENT WILL BE MADE FOR THIS WORK.

- 2.3. CONTRACTOR SHALL REPAIR ANY IRRIGATION SYSTEMS DAMAGED DURING THE COURSE OF CONSTRUCTION, PAYMENT SHALL BE INCLUDED IN RIGHT-OF-WAY CLEARING AND RESTORING. NO ADDITIONAL PAYMENTS SHALL BE MADE.
- 3. PER SECTION 402.17.2 PAYMENT FOR "SIDEWALK AND DRIVEWAY REMOVAL AND REPLACEMENT' AND PAVEMENT REMOVAL AND REPLACEMENT SHALL BE PAID FOR IN SQUARE YARDS. THE PAY QUANTITY SHALL SE COMPUTED AS THE LENGTH ALONG THE CENTERLINE OF THE PIPE BEING REPLACED MULTIPLIED BY THE STANDARD PAY WIDTH. (SEE STANDARD NO. 713)
- NOT USED.
- 5. DEVELOPED AREAS DISTURBED BY CONSTRUCTION SHALL BE RESTORED BY SODDING. HYDROMULCH SEEDING WILL BE ALLOWED IN UNDEVELOPED LOTS AT NO ADDITIONAL COST TO THE CITY OF TULSA. MAXIMUM PAY LIMIT FOR SODDING AND SEEDING SHALL BE STANDARD 10 FEET ON EITHER SIDE OF CENTERLINE OF PIPE. MAXIMUM PAY WIDTH OF 20-FEET.

6.1. THE MANHOLE RING, COVER, GROUT, WATERTIGHT SEAL, 80 MILS OF RAVEN 405 EPOXY OR APPROVED EQUAL AND OTHER MATERIALS INCIDENTAL TO THE CONSTRUCTION OF MANHOLES SHALL BE INCLUDED IN THE UNIT PRICE BID FOR EACH ASSOCIATED MANHOLE PAY ITEM; NO ADDITIONAL PAYMENT SHALL BE MADE. 4-FOOT I.D. MANHOLES AND 5-FOOT I.D. SHALLOW MANHOLES SHALL NOT BE EPOXY COATED.

6.2. ALL RISER RINGS INSTALLED ON EXISTING AND NEW MANHOLES SHALL BE CRETEX PRO-RING OR ENGINEER APPROVED EQUAL, NO CONCRETE RISER RINGS ARE PERMITTED FOR USE UNLESS APPROVED BY ENGINEER.

6.3. ALL NEW MANHOLES SHALL HAVE WALL JOINTS WRAPPED WITH 9-INCH INFI-SHIELD GATOR WRAP AS MANUFACTURED BY SEALING SYSTEMS INC. OR ENGINEER APPROVED EQUAL. (NO SEPARATE PAYMENT).

6.4. ALL NEW MANHOLES SHALL NOT HAVE STEPS AND SHALL HAVE 30-INCH LIDS.

NOT USED.

8. NOT USED.

9.1. PAVEMENT REMOVAL AND REPLACEMENT FOR WATER, SANITARY, AND STORMWATER MAIN INSTALLATIONS - WITH RESPECT TO SAW CUTTING AND DOWELS, AND INCLUDES THE FOLLOWING (THESE ITEMS SHALL NOT BE PAID SEPARATELY):

i. SAW CUTTING

ii. DOWELS

iii. DISPOSAL OF BROKEN PAVEMENT

iv. TEMPORARY SURFACES

v. ASSOCIATED EXCAVATION vi. PREPARATION OF SUBGRADE

vii. FORMS OR REINFORCING

viii. REMOVAL OR REPLACEMENT OF GRAVEL ix. ADDITIONAL SAW CUTTING OR REPLACEMENT OF PAVEMENT DAMAGED BY THE CONTRACTOR

x. JOINT SEALER, TACK COATS, OR EDGE SEALING

xi. THIS PAY ITEM DOES NOT INCLUDE THE FOLLOWING WHICH SHALL BE PAID SEPARATELY IN ACCORDANCE WITH CITY STANDARD SPECIFICATIONS, DETAILS AND DRAWINGS:

a. CURB AND GUTTER

TRAFFIC CONTROL SHALL BE IN ACCORDANCE WITH THE LATEST EDITION OF THE MANUAL ON UNIFORM TRAFFIC CONTROL DEVICES (MUTCD). THIS ITEM SHALL BE PAID PER CALENDAR DAYS FOR ALL NECESSARY TRAFFIC CONTROL.

NOT USED.

NOT USED.

12. NOT USED.

NOT USED.

14. NOT USED.

WHERE PVC SEWER PIPE IS USED, THE MATERIALS SHALL CONFORM TO THE REQUIREMENTS OF THE ASTM D-3034 LATEST REVISION, UNLESS OTHERWISE SPECIFIED. THE STANDARD DIMENSIONS RATIO OF PVC PIPE SHALL NOT EXCEED 26. REFER TO SECTIONS 405,406,407 AND 408 FOR THE REQUIREMENTS OF PIPE MATERIALS OTHER THAN PVC.

16. NOT USED.

17. NOT USED.

- 18. THE "OWNER ALLOWANCE" CAN BE USED FOR VARIOUS WORK AND MISCELLANEOUS ITEMS NOT IDENTIFIED IN THE CONTRACT DOCUMENTS WITH THE FOLLOWING PROVISIONS: THE ALLOWANCE SHALL BE USED FOR COST OF MATERIALS, LABOR, INSTALLATION AND OVERHEAD AND PROFIT FOR ADDITIONAL WORK AND MISCELLANEOUS ITEMS THAT ARE NOT IDENTIFIED IN THE CONSTRUCTION DOCUMENTS AND PLANS, AND NOT INCLUDED IN THE BID ITEMS OF THE CONTRACT.
 - A. THE ALLOWANCE SHALL BE USED ONLY AT THE DISCRETION OF THE CITY. ANY ALLOWANCE BALANCE REMAINING AT THE COMPLETION OF THE PROJECT WILL BE CREDITED BACK TO THE CITY ON THE FINAL APPLICATION FOR PAYMENT SUBMITTED BY THE CONTRACTOR.
 - B. THE CONTRACTOR SHALL PROVIDE, TO THE CITY, A WRITTEN REQUEST FOR THE USE OF ANY ALLOWANCE, WITH A SCHEDULE OF VALUES, AND ALL ASSOCIATED BACKUP INFORMATION. INCLUDING ANY TIME EXTENSIONS REQUIRED TO PERFORM THE WORK.
 - C. THE CONTRACTOR SHALL PROCEED WITH THE WORK INCLUDED IN THE ALLOWANCE ONLY AFTER RECEIVING A WRITTEN ORDER, FROM THE ENGINEER AND CITY AUTHORIZING SUCH WORK. PROCEEDING WITH WORK IN THE ALLOWANCE WITHOUT A WRITTEN ORDER FROM THE CITY WILL BE AT THE CONTRACTOR'S EXPENSE.

19. NOT USED.

20. NOT USED.

General Notes

- ALL CONSTRUCTION SHALL BE CONDUCTED IN STRICT ACCORDANCE WITH CITY OF TULSA. ENGINEERING SERVICES DEPARTMENT STANDARDS AND SPECIFICATIONS.
- 2. THE CONTRACTOR SHALL SUBMIT A CONSTRUCTION SAFETY PLAN TO THE ENGINEER PRIOR TO COMMENCEMENT OF WORK. THE SAFETY PLAN SHALL ADDRESS BUT NOT BE LIMITED TO ISSUES SUCH AS TRAFFIC CONTROL, WORK SITE SAFETY, MANHOLE VENTILATION, WORKER EQUIPMENT, FIRST AID, HYGIENE, AND OTHER RELATED TOPICS. THE CONTRACTOR WILL BE EXPECTED TO PERFORM THE WORK IN A MANNER THAT BEST PROTECTS THE SAFETY OF WORKERS. INSPECTORS, BYSTANDERS. AND OTHERS WHO MAY BE IN THE VICINITY OF THE PROJECT FAILURE TO PERFORM THE WORK AND MAINTAIN THE SITE IN A SAFE MANNER, IN THE OPINION OF THE ENGINEER OR OWNER, SHALL BE SUFFICIENT CAUSE TO STOP ALL WORK UNTIL SAFETY PROBLEMS ARE CORRECTED.
- THE CONTRACTOR SHALL HAVE ONE (1) EXECUTED COPY OF CONTRACT DOCUMENTS AT THE JOB SITE AT ALL TIMES.
- 4. UTILITIES SHOWN ON THE DRAWINGS ARE BASED ON THE ENGINEER'S REVIEW OF UTILITY ATLASES AND UTILITY COMPANY COMMENTS. CONTRACTOR IS RESPONSIBLE TO LOCATE ALL UTILITIES PRIOR TO EXCAVATING FOR MANHOLE OR PIPELINE REPAIR OR REPLACEMENT, CONTRACTOR SHALL CONTACT 1-800-CALL-OKIE (1-800-522-4543) TO LOCATE BURIED UTILITIES. UTILITIES DISTURBED BY THE CONTRACTOR SHALL BE THE CONTRACTORS FULL RESPONSIBILITY FOR REPAIR ACCORDING TO THE UTILITY'S SPECIFICATIONS AND REQUIREMENTS AT NO COST TO OWNER.
- 5. CONTRACTOR SHALL PROVIDE TEMPORARY ORANGE SAFETY FENCING AROUND ALL EXCAVATION. INCLUDING TRENCHES, PITS, VAULTS, ETC. TO MAINTAIN SECURITY AND SAFETY FOR ANIMALS, CHILDREN OR ANY BYSTANDER. THE COST FOR ORANGE SAFETY FENCE TO BE INCLUDED IN OTHER PAY ITEMS.
- 6. THE CONTRACTOR SHALL WORK IN COOPERATION WITH THE CITY OF TULSA TO ESTABLISH, INSTALL, MAINTAIN, AND OPERATE COMPLETE, ADEQUATE AND SAFE TRAFFIC CONTROLS DURING THE ENTIRE CONSTRUCTION PERIOD. FOR ALL ROAD CLOSURES, A TRAFFIC CONTROL PLAN SHALL BE SUBMITTED AND APPROVED BY CITY OF TULSA FIELD ENGINEERING. CONTRACTOR MUST NOTIFY EMSA, POLICE, FIRE AND MTTA 48 HOURS PRIOR TO STREET CLOSURE.
- 7. PRIOR TO EXCAVATING, THE CONTRACTOR IS RESPONSIBLE FOR BRACING OR SUPPORTING ANY POWER POLE OR GUY WIRE WITHIN 5 FEET OF EXCAVATION TO THE SATISFACTION OF THE OWNER AND THE UTILITY COMPANY. AT NO ADDITIONAL COST TO THE OWNER.
- 8. DRIVEWAYS, SIDEWALKS, FENCES AND OTHER AREAS PUBLIC AND PRIVATE DAMAGED BY THE CONTRACTOR SHALL BE RESTORED TO A CONDITION EQUAL TO OR BETTER THAN THAT PRIOR TO THE PROJECT AT HIS OWN EXPENSE.
- 9. ALL PAVEMENT REMOVAL SHALL BE SAW CUT AT THE NEAT LINES SHOWN ON THE PLANS OR AS INDICATED IN THE SPECIFICATIONS. SAW-CUTS REQUIRED FOR REMOVAL AND REPLACEMENT ITEMS SHALL BE FULL DEPTH OF THE EXISTING SURFACE. SAW-CUTS SHALL NOT BE PAID FOR DIRECTLY, BUT SHALL BE CONSIDERED SUBSIDIARY TO OTHER ITEMS.
- 10. ALL UNSUITABLE MATERIALS REMOVED DURING TRENCHING OR EXCAVATION SHALL BE DISPOSED OF AT A SITE APPROVED BY THE OWNER PRIOR TO TRENCHING OR EXCAVATION. THE CONTRACTOR SHALL SUBMIT THE PROPOSED DISPOSAL SITE TO THE ENGINEER FOR HIS REVIEW. STOCKPILING OF EXCAVATED MATERIAL IN STREET OR ALLEY RIGHTS-OF-WAY MAY BE ALLOWED UPON APPROVAL BY THE ENGINEER. MAINTENANCE OF STOCKPILE SITES IS THE SOLE RESPONSIBILITY OF THE CONTRACTOR. CONTRACTOR MUST MAINTAIN STOCKPILE SITES IN A SAFE. POLLUTION FREE CONDITION THROUGHOUT THE PROJECT. THE CONTRACTOR SHALL NOT STOCKPILE MATERIAL OR STORE ANY EQUIPMENT OVERNIGHT IN THE TULSA REGULATORY
- 11. ALL CONCRETE PAVEMENTS, FLEXIBLE PAVEMENTS, CURB AND GUTTER, AND UNPAVED SURFACES SHALL BE FINISHED TO MATCH EXISTING SURROUNDING SURFACES.
- 12. IN ALL AREAS WHERE EXCAVATION WILL OCCUR, CONTRACTOR SHALL VIDEOTAPE ALL CONCRETE, PAVEMENT, BUILDINGS, FOUNDATIONS, LANDSCAPING, LAWNS, AND TREES PRIOR TO CONSTRUCTION AND SUBMIT THE VIDEO DATA TO ENGINEER FOR PROJECT RECORDS.
- 13. CONTRACTOR MUST EXERCISE DILIGENCE WHEN WORKING AROUND TREES, HOWEVER IF DAMAGE OCCURS TO TREES WITHIN AN EASEMENT, THE CONTRACTOR SHALL NOT BE HELD RESPONSIBLE.
- 14. TRAFFIC ON ALL STREETS AND ACCESS TO ALL BUSINESSES SHALL BE MAINTAINED DURING REGULAR BUSINESS HOURS FOR EACH ESTABLISHMENT. CONTRACTOR MUST MAINTAIN PROPER CONSTRUCTION SIGNAGE AND TRAFFIC CONTROL IN ACCORDANCE WITH THE MANUAL ON UNIFORM TRAFFIC CONTROL DEVICES.
- 15. CONTRACTOR MUST NOTIFY HOMEOWNER A MINIMUM OF 48 HOURS PRIOR TO ANY REHAB OR CONSTRUCTION BEING DONE ON HOMEOWNERS PROPERTY
- 16. ALL HIGH-PRESSURE GAS LINES IN THE AREA OF CONSTRUCTION SHALL BE POTHOLED BY THE CONTRACTOR TO VERIFY LOCATION, COST TO BE INCLUDED IN OTHER ITEMS. NO ADDITIONAL PAYMENT WILL BE MADE.
- 17. CONTRACTOR TO BE RESPONSIBLE FOR THE PROTECTION AND RESTORATION OF ANY EXISTING STORAGE SHEDS LOCATED WITHIN THE CONSTRUCTION AREA DAMAGED DURING CONSTRUCTION, AT NO COST TO THE CITY OF TULSA OR THE HOMEOWNER.
- 18. CONTRACTOR SHALL REPAIR ANY IRRIGATION SYSTEMS DAMAGED OR DISTURBED DURING THE COURSE OF CONSTRUCTION. PAYMENT SHALL BE INCLUDED IN OTHER ITEMS. NO ADDITIONAL PAYMENT SHALL BE MADE.
- 19. ALL WATER, SANITARY SEWER, AND STORM SEWER MANHOLE CASTINGS, LIDS, FRAMES, CURB HOODS, GRATES, HYDRANTS, VALVES, AND ANY OTHER FITTINGS REMOVED AS PART OF ANY CONSTRUCTION PROJECT ARE THE PROPERTY OF THE CITY OF TULSA. CONTRACTOR WILL NOT TAKE OWNERSHIP.

ALL SANITARY AND STORM SEWER MANHOLE CASTINGS AND LIDS THAT ARE LOCATED IN THE STREET AND ARE DISTURBED BY THE CONTRACTOR SHALL BE DELIVERED TO THE SEWER OPERATIONS MAINTENANCE BASE AT 9319 E. 42ND STREET N. AND PLACED IN THE METAL RECYCLE BIN IN THE STOCKROOM AREA BETWEEN THE HOURS OF 7.30 AM AND 3.00 PM, MONDAY THROUGH FRIDAY, PHONE 918-669-6130.

ALL HYDRANTS, VALVES, AND OTHER FITTINGS FROM ABANDONED WATER MAINS SHALL BE SALVAGED AND DELIVERED BY THE CONTRACTOR TO THE SOUTH YARD AT 2317 SOUTH JACKSON AVENUE. CONTRACTOR WILL COORDINATE THE RETURN OF SUCH ITEMS WITH THE SOUTH YARD PERSONNEL AT 918-596-9401.

20. CONTRACTOR SHALL NOT DISTURB ANY NEWLY PAVED AREAS WITHOUT WRITTEN APPROVAL FROM THE OWNER.

21. CONTRACTOR SHALL NOT STORE EQUIPMENT OR MATERIAL OVERNIGHT IN THE FLOODPLAIN.





EDITION AND APPLICABLE SUPPLEMENTS.

Wilshire Trails Sanitary Sewer Improvements

CITY OF TULSA, OKLAHOMA EXISTING UNDERGROUND LINES HAVE BEEN SHOWN TO THE EXTENT KNOWN. ALL CONSTRUCTION TO BE IN STRICT ACCORDANCE WITH CURRENT CITY OF TULSA ENGINEERING PLANS STANDARD SPECIFICATIONS, INCLUDING O.D.O.T. 2019 ESTIMA

WATER AND SEWER DEPARTMENT							
PLANS AND ESTIMATE PREPARED BY:	Engineered By Design, PL 10700 Mycrs Lanc, Choctaw, OK 73020 Phone: 405.234.0980 / Email: ahale@engineeredbydesig, CA#7655 / Exp. Date 6.30.2026						

SANITARY SEWER PAY QUANTITIES & NOTES

PROJECT NO. TMUA-ES 2023-19

EVISION	BY	DATE	PLAN SCALE:	DRAWN	SD	03/2024	APPROVED		
EVISED BID ALTERNATES	SD	5/13/24	N/A	DESIGNED	EBD	03/2024			
DDED PAY ITEM	SD	5/17/24		SURVEY	LLS	02/2022			
ATERLINE QUANTITIES	SD	6/26/24	PROFILE SCALE	PROJ MGR.	6V	09/2025			
TY COMMENTS	SD	7/24/25	HORIZONTAL:	LEAD ENGR.	67/2	09/25			
TY COMMENTS	SD	7/28/25	N/A	FIELD MGR.	Fay	9/25			_
TY COMMENTS	SD	7/29/25	VERTICAL:	RECOMMENDE	Dian	9/25	12 Ola	mus	5/1
TY COMMENTS	SD	7/31/25	N/A	DESIGN MANA		1/-0	CITY ENGIN		
TY COMMENTS	SD	8/4/25	FILE:	DRAWING:			DATE:		
TY COMMENTS	SD	8/19/25	ATLAS PAGE NO:	218			SHEET 2	OF 6	SHEETS

