

PART 320 – CRADLE, CONCRETE

- 320.1 The work under this item shall include the installation of concrete cradle as shown on the Drawings or as directed by the Inspector, in accordance with the Standard Details. Care shall be taken to ensure that placing of cradle does not deflect the pipe from the proper grade and alignment.
- 320.2 Payment: Payment for this item shall be made at the unit price bid per cubic yard of concrete placed as cradle. All concrete cradle required because of excessive trench width shall be placed at the expense of the Contractor. No payment will be made for concrete used as fill or in excess of the theoretical quantity computation based on the Standard Details.