


LEGEND

- ATLAS SHEET NUMBER
177
- ATLAS SHEET BOUNDARY
- MANHOLE CALLOUT
MANHOLE NUMBER
MANHOLE DEPTH
(SEE NOTE 6 MANHOLE REHAB, PAGE 3)
80'-N
- MAINTENANCE BOUNDARY
XXXXXXX
- MAINTENANCE DISTRICT
WD
- WOOD FENCE
CL
- CHAIN LINK FENCE
OVH
- OVERHEAD UTILITIES
Ø PP
- POWER POLE
- APPROXIMATE LOCATION
OF TULSA REGULATORY
FLOODPLAIN
- STORM SEWER LINE AND INLET
SD
- CURED IN PLACE PIPE
CIPP
- MANHOLE/LAMPHOLE REPLACEMENT
□
- TOPSIDE MANHOLE/LAMPHOLE REPAIR
△
- INTERIOR MANHOLE REPAIR
○
- MANHOLE BUBBLE
MANHOLE #
- POINT REPAIR
X
- OBSTRUCTION REMOVAL
★
- LINE REPLACEMENT
OPEN CUT OR TRENCHLESS
- SLIPLINE / CIPP
■■■■■■■■



UTILITY COORDINATION INFORMATION

TULSA ENGINEERING SERVICES DEPARTMENT	596-9566
WATER DESIGN	596-9566
WASTEWATER DESIGN	596-9564
TRANSPORTATION DESIGN	596-9741
TRAFFIC ENGINEERING DESIGN	596-9741
STORMWATER DESIGN	596-9741
COOT UTILITY COORDINATION	596-9649
OKLAHOMA NATURAL GAS CO.	831-8215
COX COMMUNICATIONS	286-4716
AEP/PSO	250-6257
A/T&T	596-4217
MTTA	830-0024

SURVEY DATUM:
HORIZONTAL - OKLAHOMA STATE PLANE COORDINATE (NAD 1983)
VERTICAL - (NAVD 1988)

CONSTRUCTION PLANS FOR

CROW CREEK


SPECIFIC REMEDIATION PLAN, CONTRACT 5

TMUA PROJECT NO. ES 2024-04

WATER AND SEWER DEPARTMENT

CITY OF TULSA, OKLAHOMA

OCTOBER 2025



SHEET LIST TABLE

SHT NO.	TITLE	SHT NO.	TITLE
1	TITLE SHEET	25	ATLAS 60 - PROFILES 1
2	PAY QUANTITIES AND PAY ITEM NOTES	26	ATLAS 60 - PROFILES 2
3	PAY QUANTITIES AND PAY ITEM NOTES - ADD ALT	27	ATLAS 60 - PROFILES 3
4	GENERAL NOTES	28	ATLAS 60 - PROFILES 4
5	PROJECT LOCATION MAP	29	ATLAS 60 - PROFILES 5
6	STORMWATER MANAGEMENT PLAN	30	ATLAS 60 - PROFILES 6
7	ATLAS 14 - MANHOLE SCHEDULE	31	ATLAS 60 - PROFILES 7
8	ATLAS 14 - MANHOLE SCHEDULE	32	ATLAS 60 - PROFILES 8
9	ATLAS 14 - MANHOLE SCHEDULE	33	ATLAS 60 - PROFILES 9
10	ATLAS 14 - MANHOLE SCHEDULE	34	ATLAS 60 - PROFILES 10
11	ATLAS 14 - MANHOLE SCHEDULE	35	ATLAS 60 - PROFILES 11
12	ATLAS 14 - MANHOLE SCHEDULE	36	ATLAS 60 - PROFILES 12
13	ATLAS 14 - MANHOLE SCHEDULE	37	ATLAS 60 - PROFILES 13
14	ATLAS 14 - MANHOLE SCHEDULE	38	ATLAS 60 - PROFILES 14
15	ATLAS 14 - MANHOLE SCHEDULE	39	ATLAS 60 - PROFILES 15
16	ATLAS 14 - MANHOLE SCHEDULE	40	ATLAS 60 - PROFILES 16
17	ATLAS 14 - MANHOLE SCHEDULE	41	ATLAS 60 - PROFILES 17
18	ATLAS 14 - MANHOLE SCHEDULE	42	ATLAS 60 - PROFILES 18
19	ATLAS 14 - MANHOLE SCHEDULE	43	ATLAS 60 - PROFILES 19
20	ATLAS 14 - MANHOLE SCHEDULE	44	ATLAS 60 - PROFILES 20
21	ATLAS 14 - MANHOLE SCHEDULE		
22	ATLAS 14 - MANHOLE SCHEDULE		
23	ATLAS 14 - MANHOLE SCHEDULE		
24	ATLAS 14 - MANHOLE SCHEDULE		

CITY OF TULSA STANDARD DETAILS

- 351 - BEDDING DETAIL, PVC FLEXIBLE SANITARY SEWER PIPE
- 353 - STANDARD DETAIL, FRAME AND LID FOR 4" MANHOLE
- 354 - STANDARD DETAIL, FRAME AND LID FOR 5" AND LARGER MANHOLE
- 358 - STANDARD DETAIL, PRE-CAST SANITARY SEWER MANHOLE
- 360 - STANDARD DETAIL, FRAME AND LID FOR LAMPHOLES
- 361 - STANDARD DETAIL, IN-LINE TEES FOR SERVICE CONNECTION
- 362 - RISER DETAIL
- 363 - RISER DETAIL, WITH SLOPED TRENCH
- 401 - MANHOLE GRADE ADJUSTMENT
- 401A - CONCRETE COLLAR FOR PARTIAL MANHOLE REPLACEMENT
- 402 - COVER, FRAME, AND FRAME SEAL, REPAIR
- 403 - SPECIAL DETAIL, FOR INTERIOR COATING SYSTEM
- 404 - STEP REMOVAL
- 405 - RUBBER SEAL AT MANHOLE
- 407 - BENCH AND INVERT REHABILITATION
- 408 - EXCAVATION AND RESTORATION AT GRADE AND ABOVE GRADE CONSTRUCTION
- 409 - CONCRETE MANHOLE COLLAR
- 410 - CORBEL (CONE) REPLACEMENT
- 411 - CHEMICAL PRESSURE GROUTING PRECAST MANHOLE
- 412 - CHEMICAL PRESSURE GROUTING BRICK MANHOLE
- 413 - PATCH HOLE AND PLUG LIFT HOLE
- 414 - MANHOLE ADJUSTMENT RING
- 713 - STANDARD DETAIL, FOR PAVEMENT REMOVAL AND REPLACEMENT
- 714 - STANDARD DETAIL, FOR PAVEMENT CUTS

CITY OF TULSA SPECIFICATIONS

- 400 - GENERAL PROVISION
- 401 - SITE PREPARATION
- 402 - RESTORATION
- 403 - BACKFILL
- 404 - REMOVAL, SALVAGE, AND ABANDONMENT OF EXISTING UTILITIES
- 405 - PIPELINE AND INSTALLATION
- 406 - PIPE REAMING
- 407 - PIPE CRUSHING
- 408 - PIPE BURSTING
- 409 - SLIPLINING
- 410 - CURED-IN-PLACE PIPE
- 415 - CONSTRUCTION TELEVISION INSPECTION OF SANITARY SEWER
- 416 - COMPLETE MANHOLE REPLACEMENT
- 418 - REPLACEMENT OF MANHOLE FRAME AND COVER, FRAME SEAL, CHIMNEY, AND GRADE ADJUSTMENT
- 419 - PATCHING, REPAIRS, AND PLUGGING LIFT HOLES
- 420 - MANHOLE STEP REMOVAL AND REPLACEMENT
- 421 - INTERIOR MANHOLE REHABILITATION - CORBEL (CONE) AND WALL REHABILITATION, BENCH AND INVERT AND PIPE SEAL, REHABILITATION, EPOXY COATING
- 422 - MANHOLE TESTING OF NEW AND REHABILITATED MANHOLES
- 423 - OBSTRUCTION REMOVAL



APPROVED BY:

DIRECTOR, WATER AND SEWER DEPT.

DATE

10/10/2025



TETRA TECH

7645 E. 63rd Street, Suite 301, Tulsa, OK 74133

TEL 918.249.3909

CA NO. 2388 (EXP. 6-30-2027)

PROJECT MANAGER, TETRA TECH



DATE

PAY ITEM NOTES

1. QUANTITIES UNDER THE "EXTRA" COLUMN HEADING ARE NOT ASSOCIATED WITH ANY SPECIFIC REPAIR SHOWN ON THE PLANS AND WILL ONLY BE USED TO COMPENSATE THE CONTRACTOR FOR ADDITIONAL COSTS INCURRED DUE TO CHANGED FIELD CONDITIONS.
2. SURFACE RESTORATION ITEMS SHALL BE PAID FOR IN ACCORDANCE WITH SPECIFICATION SECTION 402.17.
3. PER SECTION 402.17.2 PAYMENT FOR "SIDEWALK AND DRIVEWAY REMOVAL AND REPLACEMENT" AND "PAVEMENT REMOVAL AND REPLACEMENT" SHALL BE PAID FOR IN SQUARE YARDS. THE PAY QUANTITY SHALL BE COMPUTED AS THE LENGTH ALONG THE CENTERLINE OF THE PIPE BEING REPLACED MULTIPLIED BY THE STANDARD PAY WIDTH. (SEE STANDARD NO. 713)
4. QUANTITY INCLUDES REQUIRED SURFACE RESTORATION FOR PLACING SERVICE LINES IN STREET R/W. NO ADDITIONAL PAYMENT WILL BE MADE FOR SURFACE RESTORATION ASSOCIATED WITH THE SERVICE LINE REPLACEMENTS.
5. THE SOD QUANTITY SHALL BE COMPUTED AS FOLLOWS - LENGTH OF GRASS ALONG SEGMENT DISTURBED x 20' WIDE DIVIDED BY 9 FOR A TOTAL SQUARE YARDS PER SEGMENT. SOD RESTORATION WIDTHS BEYOND 20' SHALL BE AT THE EXPENSE OF THE CONTRACTOR AND NO SEPARATE PAYMENT SHALL BE MADE.
6. MANHOLES WITH INTERIOR EPOXY COATINGS SHALL NOT RECEIVE STEPS. NEW MANHOLES SHALL NOT HAVE STEPS.
7. THE CONTRACTOR SHALL REMOVE ALL DEBRIS OR FOREIGN MATERIALS FROM THE MANHOLE, CORBEL, WALL, BENCH, STEPS AND INVERT. DEBRIS SHALL BE KEPT FROM ENTERING THE SEWER LINES. CONTRACTOR SHALL AT NO EXTRA COST TO OWNER, REPLACE ANY PORTION OF THE EXISTING MANHOLE WHICH IS DAMAGED DURING CLEANING.
8. STEP REMOVAL AND REPLACEMENT (TYPE I REPAIR) WHEN SPECIFIED, SHALL BE PAID FOR ON A PER MANHOLE BASIS AND INCLUDE ALL THE STEPS IN THE MANHOLE REGARDLESS OF SIZE OR HEIGHT OF THE MANHOLE.
9. TRAFFIC CONTROL SHALL BE PERFORMED IN ACCORDANCE WITH THE LATEST EDITION OF THE MANUAL ON UNIFORM TRAFFIC CONTROL DEVICES (MUTCD). THIS ITEM SHALL BE PAID PER CALENDAR DAYS FOR ALL NECESSARY TRAFFIC CONTROL. PAYMENT IS NOT GUARANTEED FOR FULL AMOUNT OF CALENDAR DAYS LISTED. PAYMENT FOR TRAFFIC CONTROL WILL BE BASED ON ACTUAL CALENDAR DAYS THAT TRAFFIC CONTROL ITEMS AND/OR DEVICES ARE USED.
10. EXTERNAL SERVICE CONNECTIONS SHALL BE REPLACED AT LEAST ONE FOOT BEYOND THE UPPER BEND. IF CUSTOMER SIDE OF SERVICE LINE IS IN POOR CONDITION, THE CONTRACTOR SHALL MAKE TEMPORARY CONNECTION AND NOTIFY QUALITY ASSURANCE FOR CUSTOMER REPAIR. CONTACT BREN SUMMERLIN AT (918) 591-4393.
11. CONTRACTOR SHALL COMPLETE A SERVICE REPORT FORM FOR EACH SERVICE RECONNECTED. THIS FORM IS PROVIDED IN THE SPECIAL PROVISIONS AND SHALL BE COMPLETED AND SUBMITTED WITH EACH MONTHLY PAY REQUEST.
12. OBSTRUCTION REMOVALS MUST BE APPROVED BY ENGINEER PRIOR TO CONSTRUCTION. ALL NECESSARY MATERIAL, LABOR, BACKFILLING, SURFACE RESTORATION, TESTING, AND INCIDENTALS SHALL BE INCLUDED. NO ADDITIONAL PAYMENT WILL BE MADE.
13. POST REHABILITATION CCTV SHALL BE INCLUDED IN THE COST OF THE REHABILITATION PAY ITEM, WITH THE EXCEPTION OF OPEN CUT, WHICH WILL BE DONE BY SEWER OPERATION MAINTENANCE. NO SEPARATE PAYMENT SHALL BE MADE.
14. FLOWABLE FILL MAY BE PERMISSIBLE WHEN NORMAL COMPACTION METHODS ARE NOT FEASIBLE. WITH ENGINEERS APPROVAL ONLY. NO MORE THAN 0.6 CY PER FOOT OF EXCAVATED DEPTH WILL BE PERMITTED.
15. WHERE PVC SEWER PIPE IS USED, THE MATERIALS SHALL CONFORM TO THE REQUIREMENTS OF THE ASTM D-3034 LATEST REVISION, UNLESS OTHERWISE SPECIFIED. THE STANDARD DIMENSIONS RATIO OF PVC PIPE SHALL NOT EXCEED 26. REFER TO SECTIONS 405.406.407 AND 408 FOR THE REQUIREMENTS OF PIPE MATERIALS OTHER THAN PVC.
16. THE CONTRACTOR SHALL INSTALL A SEALED FRAME AND COVER WHEN PERFORMING MANHOLE REPAIR TYPES "A" AND "C". WITHIN THE CITY OF TULSA REGULATORY FLOOD PLAN BOUNDARY, AS SHOWN ON THE PLANS, OR AS DIRECTED BY THE ENGINEER. (SEE SPECIFICATION SECTION 426)
17. MANHOLES REQUIRING FULL REPLACEMENT OR TYPE Fc - PRECAST CORBEL SECTION, SHALL BE CONSTRUCTED WITH NO STEPS AND TO INCORPORATE AND INCLUDE A 30" FRAME AND COVER REGARDLESS OF THE MANHOLE DIAMETER, NO ADDITIONAL PAYMENT WILL BE MADE. SEE CITY OF TULSA STANDARD DETAIL 354.
18. ALL MANHOLES DESIGNATED FOR FULL REPLACEMENT OR TYPE "Fc" REHABILITATION AND ARE WITHIN THE CITY OF TULSA REGULATORY FLOOD PLAN WILL REQUIRE THE INSTALLATION OF AN "EJ 3200 SERIES FRAME & COVER". SEE SPECIAL PROVISION 3 AND COT STD 359.
19. THIS ITEM TO BE USED AS APPROVED BY THE ENGINEER FOR SEGMENTS WHICH MAY REQUIRE NEW SERVICE LINES DUE TO OBSTRUCTIONS/OBSTACLES FORCING THE RE-ROUTING OF EXISTING SERVICE LINES. REPLACEMENT OF EXISTING SERVICE LINES IN POOR CONDITION, OR CONSTRUCTION OF UNSATISFACTORY MATERIAL, OR REPLACEMENT OF SERVICE LINES SHOWING EXCESSIVE AMOUNTS OF INFLOW OR INFILTRATION, SERVICE LINE REPLACEMENT SHALL ONLY BE PERFORMED ON LINES AUTHORIZED BY THE ENGINEER AND SHALL BE LOCATED WITHIN THE STREET ROW OR SEWER EASEMENT AND NOT ON PRIVATE PROPERTY. NO ADDITIONAL PAYMENT WILL BE MADE FOR SURFACE RESTORATION.
20. SPECIFICATION 334.2 M ONLY APPLIES TO SEGMENTS WHERE OPEN CUT REPLACEMENT OCCURS. ALSO "SPOT ELEVATIONS ON THE MAIN SEWER LINE..." CAN EITHER BE SURVEYED ELEVATIONS OR MEASURE DOWNS RELATIVE TO FINISHED GRADE.
21. THIS ITEM SHALL BE PAID FOR AT THE UNIT PRICE BID FOR EACH COMPLETE MANHOLE DROP PIPING ASSEMBLY REGARDLESS OF DEPTH OR DIAMETER OF THE ASSOCIATED MANHOLE. THIS ITEM SHALL INCLUDE ALL COST FOR EXCAVATION, BACKFILL, DEWATERING, BY PASS PUMPING, GROUT, SEALS, FITTINGS, MANHOLE MODIFICATIONS, AND ALL LABOR AND OTHER MATERIALS FOR A COMPLETE INSTALLATION PER CITY STANDARDS.
22. SERVICE RECONNECT COVERS BOTH THE RECONNECTION OF 4" AND 6" SERVICES.
23. SERVICE LINE COVERS BOTH THE INSTALLATION OF 4" AND 6" LINES.
24. CONTRACTOR SHALL VERIFY REQUIRED DEPTHS, ANGLES, AND CONNECTING LINE DIAMETERS PRIOR TO ORDERING REPLACEMENT MANHOLE COMPONENTS.
25. PAVEMENT REMOVAL AND REPLACEMENT FOR WATER, SANITARY, AND STORMWATER MAIN INSTALLATIONS - WITH RESPECT TO SAWCUTTING AND DOWELS, AND INCLUDES THE FOLLOWING: (THESE ITEMS SHALL NOT BE PAID SEPARATELY): SAW CUTTING, DOWELS, DISPOSAL OF BROKEN PAVEMENT, TEMPORARY SURFACES, ASSOCIATED EXCAVATION, PREPARATION OF SUBGRADE, FORMS OR REINFORCING, REMOVAL OR REPLACEMENT OF GRAVEL, ADDITIONAL SAW CUTTING OR REPLACEMENT OF PAVEMENT DAMAGED BY THE CONTRACTOR, JOINT SEALER, TACK COATS, OR EDGE SEALING. THIS PAYMENT ITEM DOES NOT INCLUDE THE FOLLOWING WHICH SHALL BE PAID SEPARATELY IN ACCORDANCE WITH CITY STANDARD SPECIFICATIONS, DETAILS AND DRAWINGS: CURB AND GUTTER.
26. BACKFILL UNDER ALL PAVED SURFACES SHALL BE TYPE "A" AGGREGATE BASE PLACED IN 8 INCH MAXIMUM LIFTS AND COMPACTED BY A VIBRATORY HAND TAMPER TO 95% OF THE STANDARD PROCTOR DENSITY, AS MEASURED BY THE NUCLEAR DENSITY METHOD.
27. THE CONTRACTOR SHALL BE RESPONSIBLE FOR CONTROL AND MAINTENANCE OF THE STORM WATER DRAINAGE FROM THE CONSTRUCTION SITE. STORM WATER PONDING ON THE CONSTRUCTION SITE THAT IS THE RESULT OF CONSTRUCTION WILL NOT BE ALLOWED. ALL COST ASSOCIATED WITH THE STORM WATER MANAGEMENT, AS WELL AS REMOVAL OF ALL SILT AND DEBRIS FROM ALL DRAINAGE STRUCTURES, STORM SEWER PIPES AND APPURTENANCES WITHIN THE PROJECT LIMITS AT END OF PROJECT, SHALL BE INCLUDED IN THE LUMP SUM BID FOR THIS ITEM.

ESTIMATED CONSTRUCTION QUANTITIES - ADD ALTERNATE

Add Alternate 1 - Atlas 14 - Sheets 33-37

Summary of Line Rehabilitation Schedule					
Item No.	Description	Specifications	Unit	Item Note	Atlas Sheet
					14
					Total
61	8 inch Point Repair	COT 412	(EA)	13.15	3
62	8 inch Slipline SDR 21	COT 409	(LF)	13.15	241
63	8 inch Pipeburst, DR-17 DPS HDPE	COT 408	(LF)	2.13	731
64	8 inch Open Cut Only, SDR 26 PVC	COT 405	(LF)	2.13, 14, 15, 20	163
65	10 inch Open Cut Only, SDR 26 PVC	COT 405	(LF)	2.13, 14, 15, 20	39
66	10 inch Cured-in-Place Pipe	COT 410	(LF)	13	156
67	Pavement Removal and Replacement - Asphalt	COT 402	(SY)	3.25, 26	20
68	Pavement Removal and Replacement - Concrete	COT 402	(SY)	3.25, 26	20
69	Pavement Removal and Replacement - Concrete Driveway, Sidewalk	COT 402	(SY)	3.25, 26	2
70	Curb and Gutter Removal and Replacement	COT 402	(LF)	25	10
71	Sodding	COT 402	(SY)	5	73
72	Service Reconstructions	COT 405, 408, 409, 410	(EA)	10, 11, 22	36
73	PVC Service, Schedule 40	COT 405, 408, 409, 410	(LF)	4, 10, 11, 19, 23	180
74	Video Pre-Inspection	COT 415	(LF)	13	1830

Add Alternate 2 - Atlas 33 - Sheets 38-44

Summary of Line Rehabilitation Schedule					
Item No.	Description	Specifications	Unit	Item Note	Atlas Sheet
					33
					Total
75	8 inch Point Repair	COT 412	(EA)	13.15	5
76	8 inch Slipline SDR 21	COT 409	(LF)	13.15	856
77	8 inch Cured-in-Place Pipe	COT 410	(LF)	13	343
78	8 inch Pipeburst, DR-17 DPS HDPE	COT 408	(LF)	2.13	956
79	8 inch Open Cut Only, SDR 26 PVC	COT 405	(LF)	2.13, 14, 15, 20	57
80	Sodding	COT 402	(SY)	5	387
81	Service Reconstructions	COT 405, 408, 409, 410	(EA)	10, 11, 22	44
82	PVC Service, Schedule 40	COT 405, 408, 409, 410	(LF)	4, 10, 11, 19, 23	220
83	Video Pre-Inspection	COT 415	(LF)	13	3059

REGISTERED PROFESSIONAL ENGINEER
TULSA
10/8/25
21102

SEAL

BEFORE YOU SIGN
CALL OR E-MAIL

2025

DESIGNED

TJ

01/2025

DRAWN

TJ

01/2025

CHECKED

TJ

01/2025

APPROVED

TJ

01/2025

PLANS AND ESTIMATES PREPARED BY:

TETRA TECH

7045 E 32nd Street, Suite 301, Tulsa, OK 74133

TEL: 918.248.3569

PAY QUANTITIES AND PAY ITEM NOTES ADD ALT

TULSA PROJECT NO. ES 2024-04

CROW CREEK

SPECIFIC REMEDIATION PLAN, CONTRACT 5

CITY OF TULSA, OKLAHOMA

WATER AND SEWER DEPARTMENT

PLANS SCALE

DESIGNED

TJ

01/2025

DRAWN

TJ

01/2025

CHECKED

TJ

01/2025

APPROVED

TJ

01/2025

PROJECT SCALE

PROJ. MARK

8" = 1' / 3"

LEAD ENGR

10/8/25

FIELD MARK

10/8/25

FILE

—

DATE

OCTOBER 2025

ATLAS PAGE NO.

014, 033, 060

SHEET

3 OF 14 SHEETS

GENERAL NOTES

1. THE CONTRACTOR SHALL SUBMIT A CONSTRUCTION SAFETY PLAN TO THE CITY OF TULSA FIELD ENGINEERING DEPARTMENT PRIOR TO COMMENCEMENT OF WORK. THE SAFETY PLAN SHALL ADDRESS, BUT NOT BE LIMITED TO ISSUES SUCH AS TRAFFIC CONTROL, WORK SITE SAFETY, MANHOLE VENTILATION, WORK EQUIPMENT, FIRST AID, HYGIENE, AND OTHER RELATED TOPICS. THE CONTRACTOR SHALL BE EXPECTED TO PERFORM THE WORK IN A MANNER THAT BEST PROTECTS THE SAFETY OF WORKERS, INSPECTORS, BYSTANDERS, AND OTHERS WHO MAY BE IN THE VICINITY OF THE PROJECT. FAILURE TO PERFORM THE WORK AND MAINTAIN THE SITE IN A SAFE MANNER, IN THE OPINION OF THE ENGINEER OR OWNER, SHALL BE SUFFICIENT CAUSE TO STOP ALL WORK UNTIL SAFETY PROBLEMS ARE CORRECTED.
2. ALL CONSTRUCTION AND MATERIALS SHALL BE IN ACCORDANCE WITH THE CURRENT EDITION OF THE CITY OF TULSA ENGINEERING STANDARDS AND SPECIFICATIONS, IN ACCORDANCE WITH THE SPECIAL PROVISIONS OF THIS CONTRACT, AND IN ACCORDANCE WITH ODOT STANDARDS.
3. THE CONTRACTOR SHALL HAVE ONE (1) EXECUTED COPY OF THE CONTRACT DOCUMENTS AT THE JOB SITE AT ALL TIMES.
4. THE CONTRACTOR SHALL, IN COOPERATION WITH THE CITY, DEVELOP AND SUBMIT FOR APPROVAL A TRAFFIC CONTROL PLAN (TCP), TO THE CITY OF TULSA PUBLIC WORKS, FIELD ENGINEERING. THIS TCP SHALL DETAIL SUCH MEASURES AS MAY BE REQUIRED TO TO ESTABLISH, INSTALL, MAINTAIN, AND OPERATE A COMPLETE, ADEQUATE, AND SAFE TRAFFIC CONTROL SYSTEM DURING THE ENTIRE CONSTRUCTION PERIOD. THE CONTRACTOR SHALL PLACE TRAFFIC CONTROL FLAGMEN, BARRICADES, SIGNS, SIGNALS, OR OTHER DEVICES AS MAY BE REQUIRED.
5. THE CONTRACTOR SHALL BE RESPONSIBLE FOR THE IMPLEMENTATION, PERMITTING, AND EXECUTION OF A STORMWATER POLLUTION PREVENTION PLAN (SWPP3). THE CONTRACTOR SHALL PROVIDE ALL DOCUMENTATION REQUIRED OF SWP3 FOR REVIEW AND APPROVAL OF THE PLAN BY FEDERAL, STATE, AND LOCAL AUTHORITIES. THIS INCLUDES, BUT IS NOT LIMITED TO, THE NOTICE OF INTENT AND THE NOTICE OF TERMINATION.
6. THE CONTRACTOR SHALL PROVIDE TEMPORARY ORANGE SAFETY FENCING AROUND ALL EXCAVATION, INCLUDING TRENCHES, PITS, VAULTS, ETC., TO MAINTAIN SECURITY AND SAFETY FOR ANIMALS, CHILDREN OR ANY BYSTANDER. THE COST OF ORANGE SAFETY FENCING SHALL BE INCLUDED IN OTHER PAY ITEMS.
7. PRIOR TO EXCAVATING, THE CONTRACTOR IS RESPONSIBLE FOR BRACING OR SUPPORTING ANY POWER OR UTILITY POLE OR GUY WIRE WITHIN 5 FEET OF EXCAVATION TO THE SATISFACTION OF THE OWNER AND THE UTILITY COMPANY, AT NO ADDITIONAL COST TO THE OWNER.
8. ALL EXCAVATED MATERIAL REMOVED DURING TRENCHING OR EXCAVATION SHALL BE DISPOSED OF AT A SITE APPROVED BY THE OWNER. PRIOR TO TRENCHING AND EXCAVATION, THE CONTRACTOR SHALL SUBMIT THE PROPOSED DISPOSAL SITE TO THE ENGINEER FOR REVIEW. STOCKPILING EXCAVATED MATERIALS IN STREET OR ALLEY RIGHT-OF-WAY MAY BE ALLOWED UPON APPROVAL BY THE ENGINEER. MAINTENANCE OF STOCKPILE SITE IS THE SOLE RESPONSIBILITY OF THE CONTRACTOR. CONTRACTOR MUST MAINTAIN STOCKPILE SITES IN A SAFE, POLLUTION FREE CONDITION THROUGHOUT THE PROJECT. THE CONTRACTOR SHALL NOT STOCKPILE MATERIAL OR STORE ANY EQUIPMENT OVERNIGHT IN THE TULSA REGULATORY FLOODPLAIN.
9. BACKFILL UNDER ALL PAVED SURFACES SHALL BE TYPE "A" AGGREGATE BASE PLACED IN 8" MAXIMUM LIFTS AND COMPACTED BY A VIBRATORY HAND TAMPER TO 95% OF THE STANDARD PROCTOR DENSITY, AS MEASURED BY THE NUCLEAR DENSITY METHOD.
10. THE CONTRACTOR SHALL PROVIDE A DETAILED ACCESS PLAN FOR THE CONSTRUCTION OF THE PROJECT. THE CONTRACTOR IS RESPONSIBLE FOR ALL COSTS, CONSTRUCTION ACTIVITIES, AND PERMITS THAT MAY BE NEEDED FOR THE IMPLEMENTATION OF THIS PLAN.
11. CONTRACTOR MUST NOTIFY THE HOMEOWNER A MINIMUM OF 48 HOURS (SPECIFICATION 400) PRIOR TO BEGINNING ANY REHAB WORK OR CONSTRUCTION ON HOMEOWNERS PROPERTY.

12. IN ALL AREAS WHERE EXCAVATION WILL OCCUR, CONTRACTOR SHALL VIDEO ALL CONCRETE PAVEMENT, BUILDINGS, FOUNDATIONS, LANDSCAPING, LAWNS AND TREES PRIOR TO CONSTRUCTION AND SUBMIT TO THE ENGINEER FOR PROJECT RECORDS.

13. CONTRACTOR IS RESPONSIBLE FOR THE PROTECTION AND RESTORATION OF ANY EXISTING STORAGE SHEDS, LOCATED WITHIN THE CONSTRUCTION AREA, THAT ARE DAMAGED DURING CONSTRUCTION, AT NO ADDITIONAL COST TO THE CITY OF TULSA OR THE HOMEOWNER.
14. THE CONTRACTOR SHALL BE RESPONSIBLE FOR THE VERIFICATION OF THE LOCATION OF ALL EXISTING SANITARY SEWER SERVICE LATERALS IN THE PROJECT AREA. IF ENCOUNTERED OR DAMAGED DURING CONSTRUCTION, EXISTING SERVICE LATERALS SHALL BE REMOVED AND REPLACED USING PIPE OF THE SAME SIZE AND MATERIAL, AS THE EXISTING SEWER AT THE CONTRACTORS EXPENSE.

15. CONTRACTOR MUST EXERCISE DILIGENCE WHEN WORKING AROUND TREES, HOWEVER, IF DAMAGE OCCURS TO TREES LOCATED WITHIN AN EASEMENT CONTRACTOR SHALL NOT BE RESPONSIBLE.

16. ALL PAVEMENT REMOVAL SHALL BE SAW CUT AT THE NEAT LINES AS INDICATED IN THE SPECIFICATIONS AND STANDARD DETAILS. SAW CUTS REQUIRED FOR REMOVAL AND REPLACEMENT ITEMS SHALL BE FULL DEPTH OF THE EXISTING PAVEMENT. SAW CUTS SHALL NOT BE PAID FOR DIRECTLY BUT SHALL BE CONSIDERED SUBSIDIARY TO OTHER ITEMS.
17. ALL CONCRETE PAVEMENTS, FLEXIBLE PAVEMENTS, CURB AND GUTTER, AND UNPAVED SURFACES SHALL BE FINISHED TO MATCH EXISTING SURROUNDING SURFACES.
18. CONTRACTOR SHALL BE RESPONSIBLE FOR TRENCH DEWATERING, NO SEPARATE PAVEMENT WILL BE MADE FOR THIS WORK.

19. IF ANY BRICK SANITARY MANHOLES/STRUCTURES ASSOCIATED WITH THE IDENTIFIED SEWER LINES ARE FOUND, THE CITY SHALL BE NOTIFIED BEFORE WORK COMMENCES FOR AN EVALUATION OF REHABILITATION. REHABILITATION OF ANY BRICK SANITARY MANHOLES/STRUCTURES SHALL BE BY COMPLETED MANHOLE/STRUCTURE REPLACEMENT OR BY METHODS DESCRIBED IN SPECIFICATION 418.

20. ALL SANITARY SEWER AND STORM SEWER MANHOLE CASTING AND LIDS THAT ARE DISTURBED BY THE CONTRACTOR SHALL BE REPLACED WITH NEW ONES, AND THE OLD CASTINGS AND LIDS SHALL BE DELIVERED TO THE SEWER BASE AT 9319 E. 42ND STREET N, AND PLACED IN THE METAL RECYCLE BIN IN THE STOCKROOM AREA 918-669-6130, BETWEEN THE HOURS OF 7:30 AM AND 3:00 PM MONDAY THROUGH FRIDAY.
21. ALL SANITARY SEWER MANHOLES LOCATED IN THE FLOODPLAIN SHALL BE BUILT IN ACCORDANCE WITH THE FLOODPLAIN MANHOLE SPECIFICATION WITH PADDE-LOCK LID.

22. THE CONTRACTOR SHALL SUBMIT A TRENCH EXCAVATION PLAN, SEALED BY A PROFESSIONAL ENGINEER IN THE STATE OF OKLAHOMA, FOR ALL LOCATIONS WHERE TRENCH OR SHAFT EXCAVATION EXCEEDS 20 FEET DEEP.
23. IF NECESSARY, THE CONTRACTOR SHALL BE REQUIRED TO PROVIDE BYPASS PUMPING DURING SANITARY SEWER CONSTRUCTION. CONTRACTOR SHALL SUBMIT A SEWER BYPASS PLAN PRIOR TO CONSTRUCTION.

24. CONTRACTOR SHALL MAINTAIN SEWER FLOW AT ALL TIMES DURING BYPASS PUMPING OPERATIONS. THE PUMP AND BYPASS LINES SHALL BE OF ADEQUATE CAPACITY AND SIZE TO HANDLE THE ANTICIPATED WET WEATHER FLOW. LIQUID LEVELS SHALL NOT BE ALLOWED TO OVERFLOW OR BACK-UP INTO ANY CUSTOMERS DWELLING OR BUSINESS.
25. THE COST OF BYPASS PUMPING INCLUDING THE PUMPS, LINES, LABOR AND ANY OTHER ASSOCIATED ITEMS REQUIRED TO MAINTAIN BYPASS PUMPING SHALL BE INCLUDED IN OTHER ITEMS OF WORK. NO ADDITIONAL PAYMENT WILL BE MADE FOR BYPASS PUMPING. CONTRACTOR IS REQUIRED TO SUBMIT WRITTEN BYPASS PUMPING NOTIFICATION FORM TO SEWER OPERATIONS AND MAINTENANCE AT LEAST ONE WEEK PRIOR TO BYPASS PUMPING. SEE SPECIAL PROVISIONS.

26. ALL MANHOLES, PIPE SIZES AND LENGTH, DEFECTS, SURFACE TYPES AND THEIR LOCATIONS SHOWN IN THE PLANS ARE ACCORDING TO THE BEST INFORMATION AVAILABLE TO THE ENGINEER. THE CONTRACTOR IS RESPONSIBLE TO FIELD VERIFY ALL INFORMATION AND NOTIFY THE ENGINEER OF ANY DISCREPANCIES PRIOR TO PERFORMING THE WORK.

MANHOLE REHABILITATION NOTES

1. REPLACEMENT MANHOLES SHALL HAVE FLOW LINE AND RIM ELEVATIONS SET TO MATCH THOSE OF EXISTING MANHOLES UNLESS OTHERWISE NOTED BY THE ENGINEER. FRAMES AND COVERS SHALL BE PROVIDED IN ACCORDANCE WITH SPECIFICATION REQUIREMENTS.
2. CONTRACTOR SHALL ENSURE THAT ALL MANHOLE FRAME AND COVER CASTINGS HAVE MACHINED SEATING SURFACES WITH A TIGHT FIT AND COMPLY WITH THE OTHER PROVISIONS OF THE MATERIALS SPECIFICATION.

3. ACTIVE LEAKING JOINTS OR OTHER DEFECTS OBSERVED BY THE CONTRACTOR, BUT NOT SCHEDULED FOR REHABILITATION, SHALL BE REPORTED TO THE ENGINEER IMMEDIATELY UPON DETECTION.

4. IN AREAS OF MANHOLE REPAIRS, CONTRACTOR SHALL PLACE SPOILS ON PLASTIC SHEETS, PLYWOOD OR OTHER SUITABLE GROUND PROTECTION.

5. THE MANHOLE DEPTHS SHOWN ON THE PLANS ARE FROM SURFACE, HOWEVER, ACCURATE FIELD MEASUREMENTS SHALL BE UTILIZED FOR ANY MANHOLE REPLACEMENT OR REHABILITATION.

6. ALL NEW, WALL REHABILITATION, AND REPLACEMENT MANHOLES SHALL NOT HAVE STEPS INSTALLED. MANHOLE WALL REHABILITATION TYPE Gg AND Gg REPAIRS SHALL HAVE STEPS REMOVED AND ARE CONSIDERED INCIDENTAL TO WALL REHABILITATION PAY ITEMS.

7. CONTRACTOR SHALL BE REQUIRED TO VACUUM TEST ALL NEW MANHOLE INSTALLATIONS AND EXISTING MANHOLES WHERE COMPLETE REHABILITATION IS PERFORMED, IN ACCORDANCE WITH THE CITY OF TULSA ENGINEERING STANDARDS AND SPECIFICATIONS.

8. ALL FRAMES AND COVERS FOR NEW MANHOLES INSTALLED ON THE PROJECT SHALL HAVE A MINIMUM CLEAR OPENING OF 30-INCHES REGARDLESS OF MANHOLE SIZE. NEW MANHOLE FRAMES AND COVERS INSTALLED ON EXISTING MANHOLES MAY HAVE CLEAR OPENING LESS THAN 30-INCHES WITH ENGINEER APPROVAL.

PIPELINE REHABILITATION NOTES

1. POST REHABILITATION TELEVISION INSPECTION OF LINES INSTALLED BY TRENCH-LESS METHODS SHALL BE PERFORMED BY THE CONTRACTOR AND SHALL BE INCLUDED IN THE COST OF OTHER PAY ITEMS.

2. POINT REPAIR LOCATIONS ARE APPROXIMATE AND SHALL BE DETERMINED BY THE CONTRACTORS PRE-TELEVISION INSPECTION.


3. QUANTITIES SHOWN IN THE SUMMARY TABLE ARE AN ESTIMATE OF QUANTITIES FOR THE WORK SHOWN AND DO NOT REFLECT FINAL WORK ITEM QUANTITIES NECESSARY TO REHABILITATE PIPELINE SEGMENTS.

4. POINT REPAIR(S) SHALL BE PERFORMED USING LIKE PIPE ACCORDING TO CITY OF TULSA CONSTRUCTION SPECIFICATION SECTION 412.2.1. (I.E. EXISTING VCP WILL BE REPAIRED USING VCP, EXISTING PVC WILL BE REPAIRED USING PVC, AND EXISTING DIP WILL BE REPAIRED USING DIP). IF AN OBSTRUCTION IS ENCOUNTERED DURING CLEANING AND TELEVISION INSPECTION PRIOR TO OR DURING THE INSERTION OF THE NEW LINE THROUGH THE HOST PIPE, THE CONTRACTOR HAS THE OPTION OF USING VCP OR PVC TO REPAIR THE HOST PIPE AT THE LOCATION OF THE OBSTRUCTION. IN ALL CASES, CONCRETE PIPE SHALL BE REPLACED WITH PVC.

5. PIPELINE REHABILITATION PLANS ARE FOR REFERENCE ONLY AND DO NOT DEPICT ALL OF THE EXISTING UTILITIES.

6. PIPE EMBEDMENT WILL BE AS SHOWN IN CITY OF TULSA STANDARD DETAILS EXCEPT WHERE SPECIFICALLY NOTED ON THE PLANS.

7. CONTRACTOR SHALL SUPPLY WITH HIS MONTHLY PAY REQUEST, A LIST SHOWING ALL SEWER LINES REPAIRED, THE ADDRESS OF ANY SERVICE LINES THAT ARE RECONNECTED, AND THE FOOTAGE OF THE RECONNECTION FROM THE NEAREST DOWNSTREAM MANHOLE.



TETRA TECH
7645 E. 63rd Street, Suite 301, Tulsa, OK 74133
TEL 918.248.3809

GENERAL NOTES			
TULSA PROJECT NO. ES 2024-04			
CROW CREEK			
SPECIFIC REMEDIATION PLAN, CONTRACT 5			

PLANS AND ESTIMATES PREPARED BY:			
CITY OF TULSA, OKLAHOMA			
WATER AND SEWER DEPARTMENT			
DESIGN MANAGER			
FILE	DATE	DATE	DATE
DESIGN	10/15	10/15	10/15
DRAWING	10/15	10/15	10/15
ATLAS PAGE NO.	SHEET 4 OF 44 SHEETS		

1. ALL TRAFFIC CONTROL DEVICES, CONSTRUCTION SIGNAGE, BARRICADING, ETC., SHALL BE IN ACCORDANCE WITH THE LATEST REISED EDITION OF THE MANUAL ON UNIFORM TRAFFIC CONTROL DEVICES (MUTCD). CONTRACTOR SHALL PREPARE AND SUBMIT FOR APPROVAL A TRAFFIC CONTROL PLAN (TCP).
2. THE CONTRACTOR SHALL PROVIDE 48 HOURS NOTIFICATION FOR ANY AND ALL STREET/ LANE CLOSURES, MODIFICATION, OR CHANGES TO THE TRAFFIC CONTROL MEASURES TO:


POLICE	918-596-9222
FIRE	918-596-9977
COT TRAFFIC	918-596-9744
EMSA	918-596-3043
MTA	918-585-1195
3. THE CONTRACTOR SHALL NOTIFY TRAFFIC OPERATIONS 48 HOURS PRIOR TO STARTING WORK OR PRIOR TO REMOVING OR RELOCATING ANY TRAFFIC SIGNS. ALL SIGNS SHALL BE HANDLED SO AS TO AVOID ANY DAMAGE TO THE SIGN OR POST. ALL SIGNS REMOVED DUE TO CONSTRUCTION SHALL BE REINSTALLED BY THE CONTRACTOR.
4. THE CONTRACTOR SHALL BE RESPONSIBLE FOR THE MAINTENANCE OF ALL CONSTRUCTION SIGNAGE AND BARRICADING, INCLUDING, BUT NOT LIMITED TO, WASHING, REPLACEMENT, REPOSITIONING OF DEVICES, WHEN AND WHERE IT IS DEEMED NECESSARY BY THE CITY OR THE ENGINEER. THE CONTRACTOR SHALL FURNISH AND INSTALL ANY ADDITIONAL TRAFFIC CONTROL DEVICES.
5. LOCAL AND THROUGH TRAFFIC SHALL BE MAINTAINED THROUGH THE PROJECT AREA AT ALL TIMES. LOCAL TRAFFIC TO ALL PUBLIC AND PRIVATE STREETS SHALL BE ACCESSIBLE FROM ANY DETOURS DURING THE CONSTRUCTION OF THIS PROJECT. CONTRACTOR SHALL MAINTAIN ACCESS TO DRIVEWAYS AT ALL TIMES.
6. ROADSIDE HAZARDS SHALL BE COMPLETELY BARRICADED AROUND THEIR PERIMETER FOR SAFETY OF PEDESTRIANS AND VEHICLES. NO BARRICADES SHALL BE PLACED UNTIL ALL ADVANCED SIGNING IS IN PLACE.
7. ALL CHANNELING DEVICES, TYPE III BARRICADES, ETC., SHALL BE WEIGHTED DOWN WITH A NON-HAZARDOUS MATERIAL WHEN NECESSARY OR WHEN DIRECTED BY THE CITY OR THE ENGINEER.
8. ALL ADVANCE WARNING SIGNS SHALL BE PROVIDED WITH TYPE "A" WARNING LIGHTS.
9. ALL TYPE III BARRICADES SHALL BE FURNISHED WITH A MINIMUM OF TWO (2) TYPE "A" WARNING LIGHTS.
10. ALL CHANNELING DEVICES SHALL BE PROVIDED WITH TYPE "C" WARNING LIGHTS.
11. IF WARNING LIGHTS TO BE USED ON TRAFFIC CONTROL DEVICES, TYPE "A" LIGHTS SHALL ONLY BE USED ON DEVICES WARNING OF UNEXPECTED HAZARDS, AND SHALL NOT BE USED FOR DELINEATION OF THE TRAVELED WAY. ONLY TYPE "C" WARNING LIGHTS SHALL BE USED FOR DELINEATION OF THE TRAVELED WA, AND TYPE "C" LIGHTS SHALL NOT BE USED FOR ANY OTHER PURPOSE.
12. REFLECTORIZED SHEETING ON SIGNS AND BARRICADES SHALL BE OF A CUBIC PRISMATIC TYPE AND SHALL MEET THE SPECIFICATIONS ESTABLISHED FOR ASTM D 4956-01 TYPE IX RETROREFLECTIVE SHEETING REFLECTORIZED SHEETING ON DRUMS AND TUBE

- CHANNELIZERS SHALL BE OF A HIGH INTENSITY TYPE AND SHALL MEET THE SPECIFICATIONS ESTABLISHED FOR ASTM D 4996-01 TYPE III RETROREFLECTIVE SHEETING.
- UTILITIES**
- THE LOCATIONS OF THE UTILITY LINES, AS SHOWN ON THESE DRAWINGS, ARE BASED ON AULAS INFORMATION, UTILITY COMPANY COMMENTS, AND OBSERVED FEATURES. NEITHER THE CITY NOR THE ENGINEER ASSUMES OR IMPLIES ANY RESPONSIBILITY FOR THE ACCURACY OF THIS DATA. SERVICE LINES FROM THE MAIN UTILITY LINES TO ANY BUILDING OR FACILITY MAY NOT BE SHOWN. CONTRACTOR SHALL OBTAIN THE LOCATION OF THESE FROM THE UTILITY COMPANY AND SHALL BE HELD RESPONSIBLE FOR ANY DAMAGES TO THESE LINES OR ANY OTHER LINES OR UTILITIES DURING THE CONSTRUCTION OF THIS PROJECT.
- CONTRACTOR SHALL GIVE NOTIFICATION CENTER OF THE OKLAHOMA ONE-CALL SYSTEM, INC., A MINIMUM OF TWO (2) WORKING DAYS AND A MAXIMUM OF TEN (10) WORKING DAYS PRIOR TO BEGINNING WORK IN ANY AREA. PHONE: 1-800-522-6543.
- CONTRACTOR SHALL BRACE UTILITY POLES AND GUY WIRES WITHIN 5 FEET OF AN EXCAVATION. CONTRACTOR SHALL CONTACT AND COORDINATE WITH THE PUBLIC SERVICE OF OKLAHOMA/AMERICAN ELECTRIC POWER (PSCAP) A MINIMUM OF THREE (3) WEEKS PRIOR TO ANY REQUIRED BRACING, REMOVAL, OR RELOCATION OF EXISTING UTILITY POLES.
- CONTRACTOR SHALL MEET MINIMUM CLEARANCE REQUIREMENTS SET BY PUBLIC SERVICE COMPANY OF OKLAHOMA (PSC).
- PLAN & PROFILE SHEET NOTES**
- CONTRACTOR MUST FIELD VERIFY ALL DEPTHS, DISTANCE ANGLES, AND GRADES OF EXISTING SANITARY SEWER PRIOR TO START OF CONSTRUCTION. (NO SEPARATE PAY ITEM).
- THE EXISTENCE AND LOCATION OF UNDERGROUND UTILITIES INDICATED ON THE PLANS ARE TAKEN FROM THE BEST RECORDS AVAILABLE AND ARE NOT GUARANTEED TO BE ACCURATE. THE CONTRACTOR IS RESPONSIBLE FOR MAINTAINING, SUPPORTING, AND PROTECTING THE INTEGRITY OF UNDERGROUND UTILITIES AND POWER POLES DURING CONSTRUCTION.
- THE CONTRACTOR SHALL EXCAVATE ALL BURIED UTILITY CROSSINGS AHEAD OF PIPE LAYING OR THE INSTALLATION OF SHEETING OR SHORING TO AVOID UTILITY CONFLICTS. ALL COSTS ASSOCIATED WITH THIS WORK IS CONSIDERED INCIDENTAL.
- IF DAMAGED, THE CONTRACTOR SHALL BE RESPONSIBLE FOR RESTORING EXISTING FENCES, CURBS, STREETS, DRIVEWAYS, SIDEWALKS, LANDSCAPING, STRUCTURES, ETC. TO ITS ORIGINAL OR BETTER CONDITION. NO SEPARATE PAY ITEM IF LOCATED OUTSIDE OF STANDARD CONSTRUCTION PAY LIMITS.
- TRENCH EXCAVATION PROTECTION SHALL BE ACCOMPLISHED AS REQUIRED BY THE PROVISIONS OF PART 1.926, SUBPART P-EXCAVATION, TRENCHING, AND SHORING OF THE OCCUPATIONAL SAFETY AND HEALTH'S STANDARDS AND INTERPRETATIONS.
- CONTRACTOR SHALL VERIFY AND REINSTATE ALL ACTIVE SERVICE CONNECTIONS.
- CONTRACTOR SHALL REPLACE ALL SERVICES TO WITHIN 2' OF THE EASEMENT LINE OR RIGHT-OF-WAY LINE.
- DISTANCE FROM DOWNSTREAM MANHOLE TO SERVICE CONNECTION IS APPROXIMATE. CONTRACTOR SHALL FIELD VERIFY PRIOR TO CONSTRUCTION.
- CONTRACTOR SHALL MAINTAIN ACCESS TO PRIVATE RESIDENCES AT ALL TIMES.
- WHEN REHABILITATING OR REPLACING MANHOLES, CONTRACTOR SHALL MATCH GRADE OF EXISTING OR FINISHED CONDITIONS.
- FOR ABANDONMENT, REMOVE TOP 3" OF EXISTING MANHOLE/LAMP HOLE AND FILL EXISTING SANITARY SEWER AND MANHOLE/LAMP HOLE WITH CELLULAR CONCRETE.
- ABANDONMENT SHALL BE PERFORMED AFTER CONSTRUCTION OF ALL NEW SEWER MAINS.

12. CONTRACTOR SHALL TELEPHONE ANY SANITARY SEWER LINES CALLED OUT FOR ABANDONMENT TO DETERMINE LOCATION OF ACTIVE SERVICES. ANY ACTIVE SERVICES ON AN ABANDONED LINE SHALL BE RECONNECTED TO AN EXISTING OR PROPOSED SEWER MAIN IN THE IMMEDIATE VICINITY. ENGINEER SHALL BE NOTIFIED IMMEDIATELY IF THERE IS NO SEWER MAIN IN THE VICINITY TO CONNECT THE SERVICE.



GENERAL NOTES																															
TMUA PROJECT NO. ES 2024-04																															
CROW CREEK																															
SPECIAL REMEDIATION PLAN, CONTRACT 5																															
CITY OF TULSA, OKLAHOMA																															
WATER AND SEWER DEPARTMENT																															
PLANS AND ESTIMATES PREPARED BY:																															
 TETRA TECH 7545 E. 33rd Street, Suite 301, Tulsa, OK 74133 TEL:918.248.3869																															
 BEFORE YOU DIG CALL 811		PLAN SCALE: <table border="1"> <tr> <td>DRAWN</td> <td>TI</td> <td>01/20/23</td> <td>APPROVED:</td> </tr> <tr> <td>DESIGNED</td> <td>TI</td> <td>01/20/23</td> <td></td> </tr> <tr> <td>SURVEY</td> <td>TI</td> <td>01/20/23</td> <td></td> </tr> <tr> <td>PROJ. MGR.</td> <td>SW</td> <td>10/1/23</td> <td></td> </tr> <tr> <td>LEAD ENGINEER</td> <td>ACZ</td> <td>11/14/23</td> <td></td> </tr> <tr> <td>FIELD MGR.</td> <td>BRW</td> <td>10/1/23</td> <td></td> </tr> <tr> <td>FILE</td> <td>DRWING</td> <td>---</td> <td></td> </tr> </table>		DRAWN	TI	01/20/23	APPROVED:	DESIGNED	TI	01/20/23		SURVEY	TI	01/20/23		PROJ. MGR.	SW	10/1/23		LEAD ENGINEER	ACZ	11/14/23		FIELD MGR.	BRW	10/1/23		FILE	DRWING	---	
DRAWN	TI	01/20/23	APPROVED:																												
DESIGNED	TI	01/20/23																													
SURVEY	TI	01/20/23																													
PROJ. MGR.	SW	10/1/23																													
LEAD ENGINEER	ACZ	11/14/23																													
FIELD MGR.	BRW	10/1/23																													
FILE	DRWING	---																													
HORIZONTAL VERTICAL		PROJECT SCALE: HORIZONTAL VERTICAL																													
DATE: OCTOBER 2025		DESIGN MANAGER: <i>Shawn G. [Signature]</i>																													
SHEET 5 OF 44 SHEETS		ATLAS PAGE NO.																													



STORM WATER MANAGEMENT PLAN

SITE DESCRIPTION

EROSION AND SEDIMENT CONTROLS

PROJECT LIMITS: NORTH BOUNDARY IS 15th STREET. SOUTH BOUNDARY IS 36th STREET. WEST BOUNDARY IS PEORIA AVE. EAST BOUNDARY IS DELAWARE PL.

PROJECT DESCRIPTION: SANITARY SEWER MANHOLE AND LINE REHAB IN VARIOUS LOCATIONS WITHIN THE CROW CREEK PROGRAM AREA OF TULSA'S WASTE WATER COLLECTION SYSTEM.

SUGGESTED SEQUENCE OF EROSION CONTROL ACTIVITIES:

- 1. PLACE TEMPORARY SEDIMENT CONTROL DEVICES AT ALL DRAINAGE LOCATIONS.
- 2. PERFORM CLEARING AND GRUBBING OPERATIONS, PRESERVING ANY EXISTING VEGETATION NOT IMPEDING CONSTRUCTION.
- 3. REMOVE AND STOCKPILE TOPSOIL AS APPLICABLE.
- 4. ADD TEMPORARY SEDIMENT CONTROL DEVICES AND MAINTAIN THEM AS NEEDED.
- 5. AS TRENCHING AND GRADING PROCEEDS, PLACE TEMPORARY SEEDING AND/OR MULCHING OR PERMANENT GRASS COVER DEPENDING ON FINISHED GRADE AND SLOPES.
- 6. AS PERMANENT GRASS COVER IS ESTABLISHED (70% COVER), REMOVE TEMPORARY SEDIMENT CONTROL DEVICES.
- 7. ALL EROSION CONTROL ACTIVITIES SHALL BE PAID FOR UNDER PAY ITEM - SWPPP DOCUMENTATION & MANAGEMENT.

SOIL TYPE: VARIABLE
TOTAL AREA OF THE CONSTRUCTION SITE: 1280 ACRES

ESTIMATED AREA TO BE DISTURBED: 0.25 ACRES

OFFSITE AREA TO BE DISTURBED: (FOR CONTRACTOR USE)

TOTAL IMPERVIOUS AREA PRE-CONSTRUCTION: 0.014 ACRES

TOTAL IMPERVIOUS AREA POST-CONSTRUCTION: 0.014 ACRES

POST-CONSTRUCTION RUNOFF COEFFICIENT OF THE SITE: VARIABLE - NO CHANGE PRE TO POST CONSTR.

LATITUDE & LONGITUDE OF CENTER OF PROJECT: 36°07'34.49" N / 95°57'38.30 W

PROJECT WILL DISCHARGE TO:

NAME OF RECEIVING WATERS: CROW CREEK, THEN ARKANSAS RIVER

SENSITIVE WATERS OR WATERSHEDS: YES NO X

303(d) IMPAIRED WATERS: YES NO X

IF YES, LIST IMPAIRMENT:

LOCATED IN A TMDL: YES NO X

LAKE THUNDERBIRD TMDL: NO X

MS4 ENTITY: YES NO X

IF YES, LOCATION:

NOTE: THIS SHEET SHOULD BE USED IN CONJUNCTION WITH A DRAINAGE MAP THAT ILLUSTRATES THE DRAINAGE PATTERNS/PATHWAYS AND RECEIVING WATERS FOR THIS PROJECT. THIS SHEET SHOULD ALSO BE USED WITH THE EROSION CONTROL SUMMARIES, PAY ITEMS, & NOTES.

SOIL STABILIZATION PRACTICES:

- TEMPORARY SEEDING
- X PERMANENT SODDING, SPRIGGING OR SEEDING
- VEGETATIVE MULCHING
- SOIL RETENTION BLANKET
- X PRESERVATION OF EXISTING VEGETATION

NOTE: TEMPORARY EROSION CONTROL METHODS MUST BE USED ON ALL DISTURBED AREAS WHERE CONSTRUCTION ACTIVITIES HAVE CEASED FOR OVER 14 DAYS. METHODS USED WILL BE AS SHOWN ON PLANS, OR AS DIRECTED BY THE ENGINEER.

STRUCTURAL PRACTICES:

- STABILIZED CONSTRUCTION EXIT
- X TEMPORARY SILT FENCE
- TEMPORARY SILT DIKES
- X TEMPORARY FIBER LOG
- DIVERSION, INTERCEPTOR OR PERIMETER DIKES
- DIVERSION, INTERCEPTOR OR PERIMETER SWALES
- ROCK FILTER DAMS
- TEMPORARY SLOPE DRAIN
- PAVED DITCH W/ DITCH LINER PROTECTION
- TEMPORARY DIVERSION CHANNELS
- TEMPORARY SEDIMENT BASINS
- TEMPORARY SEDIMENT TRAPS
- TEMPORARY SEDIMENT FILTERS
- X TEMPORARY SEDIMENT REMOVAL
- RIP RAP
- INLET SEDIMENT FILTER
- TEMPORARY BRUSH SEDIMENT BARRIERS
- SANDBAG BERMES
- TEMPORARY STREAM CROSSINGS

OFFSITE VEHICLE TRACKING:

- HAUL ROADS DAMPENED FOR DUST CONTROL
- X LOADED HAUL TRUCKS TO BE COVERED WITH TARP/AULIN
- X EXCESS DIRT ON ROAD REMOVED DAILY

NOTES:

- SILT FENCE SHALL BE REMOVED FROM TEMPORARY EROSION CONTROL DEVICES WHEN HALF FULL.
- COST TO BE INCLUDED IN PRICE BID FOR SWPPP
- DOCUMENTATION AND MANAGEMENT.

THE CONTRACTOR SHALL ALSO BE RESPONSIBLE FOR THE FOLLOWING:

MAINTENANCE AND INSPECTION:

ALL EROSION AND SEDIMENT CONTROLS WILL BE MAINTAINED IN GOOD WORKING ORDER FROM THE BEGINNING OF CONSTRUCTION UNTIL AN ACCEPTABLE VEGETATIVE COVER IS ESTABLISHED. INSPECTION BY THE CONTRACTOR AND ANY NECESSARY REPAIRS SHALL BE PERFORMED ONCE EVERY 7 CALENDAR DAYS AND WITHIN 24 HOURS AFTER ANY STORM EVENT GREATER THAN 0.5 INCH AS RECORDED BY A NON-FREEZING RAIN GAUGE TO BE LOCATED ON SITE. POTENTIALLY ERODIBLE AREAS, DRAINAGEWAYS, MATERIAL STORAGE, STRUCTURAL DEVICES, CONSTRUCTION ENTRANCES AND EXITS ALONG WITH EROSION AND SEDIMENT CONTROL LOCATIONS ARE EXAMPLES OF SITES THAT NEED TO BE INSPECTED.

WASTE MATERIALS:

PROPER MANAGEMENT AND DISPOSAL OF CONSTRUCTION WASTE MATERIAL IS REQUIRED BY THE CONTRACTOR. MATERIALS INCLUDE STOCKPILES, SURPLUS, DEBRIS AND ALL OTHER BY-PRODUCTS FROM THE CONSTRUCTION PROCESS. PRACTICES INCLUDE DISPOSAL, PROPER MATERIALS HANDLING, SPILL PREVENTION AND CLEANUP MEASURES. CONTROLS AND PRACTICES SHALL MEET THE REQUIREMENTS OF ALL FEDERAL, STATE AND LOCAL AGENCIES.

HAZARDOUS MATERIALS:

PROPER MANAGEMENT AND DISPOSAL OF HAZARDOUS WASTE MATERIALS IS REQUIRED. THE CONTRACTOR IS RESPONSIBLE FOR FOLLOWING MANUFACTURER'S RECOMMENDATIONS, STATE AND FEDERAL REGULATIONS TO ENSURE CORRECT HANDLING, DISPOSAL, SPILL PREVENTION AND CLEANUP MEASURES. EXAMPLES INCLUDE BUT ARE NOT LIMITED TO: PAINTS, ACIDS, CLEANING SOLVENTS, CHEMICAL ADDITIVES, CONCRETE CURING COMPOUNDS AND CONTAMINATED SOILS.

GENERAL NOTES:

A STORM WATER POLLUTION PREVENTION PLAN (SWPPP) IS REQUIRED TO COMPLY WITH THE OKLAHOMA POLLUTION DISCHARGE ELIMINATION SYSTEM (OPDES) REGULATIONS. THIS PLAN IS INITIATED DURING THE DESIGN PHASE, CONFIRMED IN THE PRE-WORK MEETINGS AND AVAILABLE ON THE JOB SITE ALONG WITH COPIES OF THE NOTICE OF INTENT (NOI) FORM AND PERMIT CERTIFICATE THAT HAVE BEEN FILED WITH THE OKLAHOMA DEPARTMENT OF ENVIRONMENTAL QUALITY (ODEQ). THE PLAN MUST BE KEPT CURRENT WITH UP-TO-DATE AMENDMENTS DURING THE PROGRESSION OF THE PROJECT. ALL CONTRACTOR OFF-SITE OPERATIONS ASSOCIATED WITH THE PROJECT MUST BE DOCUMENTED IN THE SWPPP, I.E., BORROW PITS, WORK ROADS, DISPOSAL SITES, ASPHALT/CONCRETE PLANTS, ETC. THE BASIC GOAL OF STORM WATER MANAGEMENT IS TO IMPROVE WATER QUALITY BY REDUCING POLLUTANTS IN STORM WATER DISCHARGES. RUNOFF FROM CONSTRUCTION SITES HAS A POTENTIAL FOR POLLUTION DUE TO EXPOSED SOILS AND THE PRESENCE OF HAZARDOUS MATERIALS USED IN THE CONSTRUCTION PROCESS. THE PREVENTION OF SOIL EROSION, CONTAMINMENT OF HAZARDOUS MATERIALS AND/OR THE INTERCEPTION OF THESE POLLUTANTS BEFORE LEAVING THE CONSTRUCTION SITE ARE THE BEST PRACTICES FOR CONTROLLING STORM WATER POLLUTION.

THE FOLLOWING SECTIONS OF THE 2019 ODOT STANDARD SPECIFICATIONS SHOULD BE NOTED:

- 103.05 BONDING REQUIREMENTS
- 104.10 FINAL CLEANING UP
- 104.12 CONTRACTOR'S RESPONSIBILITY FOR WORK
- 104.13 ENVIRONMENTAL PROTECTION
- 106.08 STORAGE AND HANDLING OF MATERIAL
- 107.01 LAWS, RULES AND REGULATIONS TO BE OBSERVED
- 107.20 STORM WATER MANAGEMENT
- 220 MANAGEMENT OF EROSION, SEDIMENTATION AND STORM WATER POLLUTION PREVENTION AND CONTROL
- 221 TEMPORARY SEDIMENT CONTROL

IN ADDITION:

"ODEQ GENERAL PERMIT (OKR10) FOR STORM WATER DISCHARGES FROM CONSTRUCTION ACTIVITIES WITHIN THE STATE OF OKLAHOMA," ODEQ, WATER QUALITY DIVISION, NOVEMBER 1, 2023.

ADDITIONAL PERMITS REQUIRED FROM OKLAHOMA WATER RESOURCES BOARD



STORMWATER MANAGEMENT PLAN			
TMUA PROJECT NO. ES 2024-04			
CROW CREEK			
SPECIFIC REMEDIATION PLAN, CONTRACT 5			
CITY OF TULSA, OKLAHOMA			
WATER & SEWER DEPARTMENT			
PLANS AND ESTIMATES PREPARED BY:			
TETRA TECH			
7645 E. 63rd Street, Suite 301, Tulsa, OK 74133			
TEL: 918.248.3909			
PLAN SCALE	DRAWN	DESIGNED	APPROVED:
N/A			
PROFILE SCALE	SURVEY		
HORIZONTAL:	PROJ. MGR.	SV	10/15
VERTICAL:	LEAD MGR.	10/15	
FILE:	FIELD MGR.	10/15	
ATLAS PAGE NO.	DATE:	DESIGN MANAGER	
	OCTOBER 2025		
	SHEET NO.	7 OF 14	

MANHOLE BUBBLE

MANHOLE #

MANHOLE DEPTH (per atlas)

MANHOLE/PIPE REPLACEMENT

TOPSIDE MANHOLE/PIPE REPLACEMENT

INTERIOR MANHOLE REPAIR

APPROXIMATE LOCATION OF TULSA REGULATORY FLOODPLAIN

LEGEND

POINT REPAIR

LINE REPLACEMENT

OPEN CUT OR PIPEBURST

SUPLINE OR CIPP

COULD NOT LOCATE or ACCESS. RECOMMENDATION TO BE MADE DURING CONSTRUCTION

CNL

NOTE:
REFER TO LINE REHAB SCHEDULE TO DETERMINE IF LINE REHAB IS OPEN CUT OR PIPEBURST, SUPLINE OR CIPP.

CONTRACTOR SHALL NOT STOCKPILE MATERIAL OR STORE ANY EQUIPMENT OVERNIGHT IN THE TULSA REGULATORY FLOODPLAIN

0 100 200 400
SCALE: 1"=200'

REVISION
BY
DATE

DESIGNED
T1
9/1/2024

SURVEY
T1
9/1/2024

PROJ. MGR.
SM
9/1/24

LEAD ENGR.
JL
10/3/24

FIELD MGR.
JL
10/3/24

DATE
OCTOBER 2025

APPROVED
JL
10/3/24

DESIGN MANAGER
JL
10/3/24

ATLAS 14
TULSA PROJECT NO. ES 2024-04
CROW CREEK
SPECIFIC REMEDIATION PLAN, CONTRACT 5
CITY OF TULSA, OKLAHOMA
WATER AND SEWER DEPARTMENT
PLANS AND ESTIMATES PREPARED BY:
TETRA TECH
17645 E. 53rd Street, Suite 301, Tulsa, OK 74133
TEL: 918.248.2099

REGISTERED PROFESSIONAL ENGINEER
OKLAHOMA
24102
J. L. MITCHELL
J. L. MITCHELL
J. L. MITCHELL

ATLAS PAGE NO. 14
SHEET 8 OF 44 SHEETS

ATLAS 14 - MANHOLE REHAB SCHEDULE

[illegible]

REHABILITATION METHODS

TYPE A
REPLACEMENT OF MANHOLE COVER, FRAME AND
FRAME SEAL (418)

TYPE B

REPLACEMENT OF MANHOLE FRAME SEAL (418)

TYPE C

REPLACEMENT OF MANHOLE COVER, FRAME, FRAMER SEAL AND CHIMNEY (418)

TYPE D
REPLACEMENT OF MANHOLE FRAME SEAL AND CHIMNEY
(418)

TYPE Fc
PRECAST CORBEL SECTION (418)

TYPE Gg
INTERIOR MANHOLE WALL REHABILITATION (421)

TYPE Gb

TYPE GK
PIPE SEAL REHABILITATION (421)

TYPE Go

PLUG LIFT HOLES, PLUG HOLES (419)

REPLACEMENT OF MANHOLE STEPS – AT THE TIME OF MANHOLE REHABILITATION, MANHOLE STEPS SHALL BE EVALUATED AND REPLACED ON A PER-MANHOLE BASIS, AND INCLUDE ALL THE STEPS IN THE MANHOLE REGARDLESS OF SIZE OR HEIGHT OF THE MANHOLE. (420)

OR HEIGHT OF THE MANHOLE. (420)

TYPE I

CLEAN MANHOLE (Special)

MANHOLE REPLACEMENT
COMPLETE MANHOLE REPLACEMENT (416)

MANHOLE REPLACEMENT
ADDITIONAL FOOTAGE (416)

LAMPHOLE REPLACEMENT


LAMPHOLE REPLACEMENT (417)




TETRA TECH
7645 E. 63rd Street, Suite 301, Tulsa, OK 74133
TEL 918.249.3909

16.4' (Italicised) - DENOTES MANHOLE DEPTH FROM CITY OF TULSA ATLAS

	PLAN SCALE:	DATE	BY	REVISION
DRAWN	T1	01/2025		
DESIGNED	T1	01/2025		
SURVEY	T1	01/2025		
PROJ MGR	\$V	19/25		
PHONE SCALE				
HORIZONTAL				
VERTICAL				
FIELD MGR				
DRAWING:				
FILE				
ATLAS PAGE NO.	14			

APPROVED:

 DESIGN MANAGER
 DATE: OCTOBER 2025
 SHEET 9 OF 44 SHEETS

CONTRACTOR SHALL NOT STOCKPILE MATERIAL OR
STORE ANY EQUIPMENT OVERNIGHT IN THE TULSA
REGULATORY FLOODPLAIN



LEGEND

- | | | |
|---------------------------------|---|---|
| MANHOLE/LAMPPOLE REPLACEMENT |  | POINT REPAIR |
| TOPSIDE MANHOLE/LAMPPOLE REPAIR |  | LINE REPLACEMENT
OPEN CUT OR PIPEBURST |
| INTERIOR MANHOLE REPAIR |  | SUPLINE OR CIPP |


APPROXIMATE LOCATION
OF TULSA REGULATORY
FLOODPLAIN

MANHOLE BUBBLE	MANHOLE #	MANHOLE DEPTH (per atlas)
		

COULD NOT LOCATE or ACCESS.
RECOMMENDATION TO BE MADE
DURING CONSTRUCTION

CNL

NOTE:
REFER TO LINE REHAB SCHEDULE TO DETERMINE IF LINE
REHAB IS OPEN CUT OR PIPEBURST, SLIPLINE OR CIPP.



CONTRACTOR SHALL NOT STOCKPILE MATERIAL OR
STORE ANY EQUIPMENT OVERNIGHT IN THE TULSA
REGULATORY FLOODPLAIN

ATLAS 33 TMUA PROJECT NO. ES 2024-04 CROW CREEK CITY OF TULSA, OKLAHOMA WATER AND SEWER DEPARTMENT REGISTERED PROFESSIONAL ENGINEER OKLAHOMA 21102 10/19/25 FRANK MINTASH <i>Frank Mintash</i>									
PLANS AND ESTIMATES PREPARED BY:									
TF TETRA TECH 7514 E. 55th Street, Suite 301, Tulsa, OK 74133 TEL: 918.495.3589									
REVISION		BY		DATE		PLAN SCALE:			
						DRAWN: T1: 01/20/25			
						DESIGNED: T1: 01/20/25			
						SURVEY: T1: 01/20/25			
						PROFILE SCALE: SV 10/15			
						HORIZONTAL:			
						VERTICAL:			
						LEAD ENGR: <i>6/21/25</i>			
						FIELD MGR: <i>6/21/25</i>			
						DRAWING: <i>6/21/25</i>			
						FILE: <i>DESIGN MANAGER</i>			
						ATLAS PAGE NO. 33			
DATE: OCTOBER 2025 SHEET 10 OF 44 SHEETS <i>Shannon G. Orr</i>									

ATLAS 33- LINE REHAB SCHEDULE

[illegible]

ATLAS 33 - LINE SCHEDULE TMUA PROJECT NO. ES 2024-04 CROW CREEK CITY OF TULSA, OKLAHOMA WATER AND SEWER DEPARTMENT PLANS AND ESTIMATES PREPARED BY:									
TETRA TECH 7646 E. 83rd Street, Suite 301, Tulsa, OK 74133 TEL: 918.248.3569									
REGISTERED PROFESSIONAL ENGINEER OKLAHOMA 10/9/25 KEVIN MITTASCH 24102									
BEFORE YOU DIG CALL 811									
REVISION	BY	DATE	PLAN SCALE:						
			BROWN	T1	01/20/25	APPROVED:			
			DESIGNED	T1	01/20/25				
			SURVEY	T1	01/20/25				
			PROJ. MGR.	81	10/15				
			LEAD ENGINEER	612	10/15				
			FIELD MGR.	1015	10/15				
			VERTICAL						
			PROFILE SCALE						
			HORIZONTAL						
			FILE						
			DRAWINGS:						
			ATLAS PAGE NO.	33					
DATE: OCTOBER 2025 DESIGN MANAGER SHEET 11 OF 44 SHEETS									

ATLAS 33 - MANHOLE REHAB SCHEDULE

Atlas	Basin	MH	Diameter (ft)	Depth (ft) (Rim to Invert)	Grade to Rim	Drop Manhole	Address	Surface Type	TYPE A (EA)	TYPE B (EA)	TYPE C (EA)	TYPE D (EA)	TYPE Fc (EA)	TYPE Gc (SF)	TYPE Gb (EA)	TYPE Gk (EA MH)	TYPE Gc (EA MH)	TYPE Gc (EA)	TYPE Gc (EA MH)	TYPE Gc (SF)	MANHOLE REPLACEMENT, 4' ID. (EA)	Additional Depth OVER 6' FOR 4' ID. (VF)	DROP MANHOLE REPLACEMENT, 4' ID. (EA)	Additional Depth OVER 6' FOR 4' ID. DROP (VF)	MANHOLE REPLACEMENT 5' ID. (EA)	Additional Depth OVER 6' FOR 5' ID. (VF)	DROP MANHOLE REPLACEMENT 5' ID. (EA)	Additional Depth OVER 6' FOR 5' ID. DROP (VF)	LAMPHOLE REPLACEMENT (EA)	REPLACE LAMPHOLE FRAME AND COVER (EA)	SEALED LD REPLACEMENT (EA)	MANHOLE STEP REMOVAL AND TYPE (PER MH)
33	44	044-0178	4	13.55	0	No	2435 S Peoria Ave	Grass/Dirt														1	7.6									
33	44	044-0179	4	13.31	0	No	2435 S Peoria Ave	Grass/Dirt														1	7.3									
33	44	044-0234	4	11.06	0.6	No	1516 E 21st St	Grass/Dirt				1																				
33	44	044-0237	4	12.44	.02	No	2124 S Saint Louis Ave	Grass/Dirt									1															
33	44	044-0244	4	9.05	0.6	No	2112 Terwilliger Blvd	Grass/Dirt																								
33	44	044-0245	4	13.5	0	No	2208 Terwilliger Blvd	Grass/Dirt									1															
33	44	044-0247	4	13.39	0	Yes	2124 S Saint Louis Ave	Concrete Collar																								
33	44	044-0249	4	10.69	0	No	2227 Terwilliger Blvd	Grass/Dirt									1															
33	44	044-0250	4	14.4	0	No	1570 E 22nd Pl	Grass/Dirt																								
33	44	044-0251	4	13.84	0	No	2240 S Troost Ave	Grass/Dirt									1															
33	44	044-0253	4	8.32	0.22	No	2431 S Trenton Ave	Grass/Dirt																								
33	44	044-0254	0.657	7.09	-0.2	No	1615 E 26th St	Grass/Dirt																								
33	44	044-0257	4	10.5	0.35	No	2225 S Troost Ave	Grass/Dirt				1																				
33	44	044-0260	4	9.6	0	No	2201 S Saint Louis Ave	Grass/Dirt														1	3.6									
33	44	044-0261	4	9.25	1.1	No	1565 E 22nd Pl	Grass/Dirt																								
33	44	044-0541	6	13.42	0	Yes	1368 E 21st St S	Grass/Dirt											1													
33	44	044-0545	4	21.1	0	Yes	1411 E 21st St	Grass/Dirt											1													
33	44	044-0585	0.657	6.00	-4.15	No	2100 S Ultra Ave	Concrete Pavement														1										
33	44	044-0595	4	8.48	0	No	2214 S Ultra Ave	Grass/Dirt																								
33	44	044-0596	0.657	6.7	0.2	No	1655 E 22nd Pl	Grass/Dirt														1	0.7									
33	45	045-0040	4	10.08	0	Yes	1304 E 26th Pl	Grass/Dirt																								
33	45	045-0041	4	13.45	-0.24	No	1303 E 26th Pl	Grass/Dirt									1															
33	45	045-0042	4	13.68	2.02	Yes	1323 E 26th Pl	Concrete Pavement																								
33	45	045-0044	0.657	9.2	0	No	1363 E 26th Pl	Grass/Dirt																								
33	45	045-0045	4	17.8	0	No	1318 E 25th St	Grass/Dirt																								
33	45	045-0046	0.657	12.95	0	No	1305 E 26th St	Grass/Dirt														1	7.0									
33	45	045-0047	4	14.4	0	Yes	1336 E 25th St	Grass/Dirt																								
33	45	045-0735	4	7.80	0	No	1324 E 26th St	Concrete Collar																								
33	45	045-0824	4	6.46	0	No	1304 E 26th Pl	Grass/Dirt																								
33	62	062-0001	4	8.74	1.40	No	1803 E 27th St	Grass/Dirt									1															
33	62	062-0002	Not Found	17.65	UNK	No	2546 S Yorktown Ave	Grass/Dirt																								
33	62	062-0003	4	16.2	0	No	2544 S Yorktown Ave	Asphalt									1															
33	62	062-0005	4	17.54	0	No	2560 S Yorktown Ave	Grass/Dirt														1										
33	62	062-0012	4	15.9	0	No	2520 S Yorktown Ave	Grass/Dirt																								
33	62	062-0014	4	14.83	0	No	2004 E 22nd Pl	Other									1															
33	62	062-0015	4	15.6	0	No	2049 E 22nd Pl S	Asphalt																								
33	62	062-0021	4	20.09	0.3	No	2057 E 22nd Pl S	Gravel									1					1	14.1									
33	62	062-0982	4	18.15	0	No	2520 S Yorktown Ave	Grass/Dirt																								
33	62	062-1049	4	18	0	Yes	2055 E 22nd Pl S	Gravel									1															
33	62	062-1055	4	9.9	0	No	1824 E 22nd Pl	Grass/Dirt											1													
33	62	062-1056	4	15.42	0	Yes	1824 E 22nd Pl	Concrete Collar											1													

MH 062-0002 IS LISTED AS "NOT FOUND". ACTUAL REHABILITATION WILL BE DETERMINED BY ONSITE ENGINEER DURING LINE SEGMENT 062-0003 TO 062-0002 CONSTRUCTION.

REHABILITATION METHODS

- TYPE A
REPLACEMENT OF MANHOLE COVER, FRAME AND FRAME SEAL (418)

TYPE B
REPLACEMENT OF MANHOLE FRAME SEAL (418)

TYPE C
REPLACEMENT OF MANHOLE COVER, FRAME, FRAME SEAL AND CHIMNEY (418)

TYPE D
REPLACEMENT OF MANHOLE FRAME SEAL AND CHIMNEY (418)

TYPE Fe
PRECAST CORBEL SECTION (418)

TYPE Gg
INTERIOR MANHOLE WALL REHABILITATION (421)

TYPE Gh
BENCH AND INVERT REHABILITATION (419)

TYPE Gk
PIPE SEAL REHABILITATION (421)

TYPE Gc
PLUG LIFT HOLES, PLUG HOLES (419)
- TYPE Gp
SEAL PRE-CAST JOINTS (421)

TYPE Gr
PATCH HOLE (419)

TYPE Gs
EPOXY COATING (421)

TYPE L
REPLACEMENT OF MANHOLE STEPS – AT THE TIME OF MANHOLE REHABILITATION, MANHOLE STEPS SHALL BE EVALUATED AND REPLACED ON A PER-MANHOLE BASIS, AND INCLUDE ALL THE STEPS IN THE MANHOLE REGARDLESS OF SIZE OR HEIGHT OF THE MANHOLE. (420)

TYPE I
CLEAN MANHOLE (Spec'd)

MANHOLE REPLACEMENT COMPLETE MANHOLE REPLACEMENT (416)

MANHOLE REPLACEMENT ADDITIONAL FOOTAGE (416)

LAMPHOLE REPLACEMENT LAMPHOLE REPLACEMENT (417)

16.4' (italicized) - DENOTES MANHOLE DEPTH FROM CITY OF TULSA ATLAS

CONTRACTOR SHALL NOT STOCKPILE MATERIAL OR STORE ANY EQUIPMENT OVERNIGHT IN THE TULSA REGULATORY FLOODPLAIN

REGISTERED PROFESSIONAL ENGINEER
10/16/15
MITSCH
21102
OKLAHOMA

BEFORE YOU DIG
CALL OR DIG
811

ATLAS 33 - MANHOLE SCHEDULE

TULSA PROJECT NO. ES 2024-04

CROW/CREEK

SPECIFIC REMEDIATION PLAN, CONTRACT 5

CITY OF TULSA, OKLAHOMA

WATER AND SEWER DEPARTMENT

PLANS AND ESTIMATES PREPARED BY:

TETRA TECH

7645 E. 83rd Street, Suite 301, Tulsa, OK 74133

TEL: 918.248.3909

REVISION

BY

DATE

PLAN SCALE

DRAWN

TI

01/02/24

APPROVED

DESIGNED

TI

01/02/24

SURVEY

TI

01/02/24

PROFILE SCALE

PROJ. MGR.

SN

10/25

HORIZONTAL

LEAD ENGR.

10/25

FIELD MGR.

10/25

VERICAL




FILE

DRAWING

ATLAS PAGE NO. 33

DATE: OCTOBER 2025

SHEET 12 OF 44 SHEETS



APPROXIMATE LOCATION EXISTING SERVICE TAP,
CONTRACTOR TO VERIFY LOCATIONS THROUGH
PRECONSTRUCTION CCTV DATA

NOTE:
FOR LINE WORK IN PAVED AREAS, PAYMENT AND
TRENCHING TO BE COMPLETED PER CITY OF TULSA
STD. 713.

GAS LINE LOCATIONS SHOWN ARE FROM OKLAHOMA
NATURAL GAS ATLAS AND ARE APPROXIMATE

REGISTERED PROFESSIONAL ENGINEER
TULSA, OKLAHOMA
10/9/25
2102

BEFORE YOU DIG
CALL 811
TULSA, OKLAHOMA

ATLAS 33 - DETAILS
TULSA PROJECT NO. ES 2024-04
CROW CREEK
SPECIFIC REMEDIATION PLAN, CONTRACT 5
CITY OF TULSA, OKLAHOMA
WATER AND SEWER DEPARTMENT

TETRA TECH
7645 E 63rd Street, Suite 301, Tulsa, OK 74133
TEL 918.249.3909

PLANS AND ESTIMATES PREPARED BY:
DESIGN MANAGER
DATE: OCTOBER 2025
SHEET 13 OF 44 SHEETS

REVISION	BY	DATE

PLAN SCALE	DRAWN	TI	01/2/2025	APPROVED
DESIGNED	TI	01/2/2025		
SURVEY	TI	01/2/2025		
PROJECT SCALE				
HORIZONTAL				
VERTICAL				
FIELD WORK				
DATE				

FILE: ATLAS PAGE NO. 33

DATE: OCTOBER 2025

DESIGN MANAGER

DATE: OCTOBER 2025

SHEET 13 OF 44 SHEETS

ATLAS 59 - LINE REHAB SCHEDULE

Video Year	Atlas	US Rim to Invert	D/S Manhole Invert	DS Rim to Invert	Diameter	Material	CCTV Length	Incomplete CCTV (Feet estimated)	8" - Point Repair (EA)	10" - Point Repair (EA)	15" - Point Repair (EA)	Point Repair Location	8" - Add'l Footage (LF)	10" - Add'l Footage (LF)	15" - Add'l Footage (LF)	8" - Slope SR 21 (LF)	8" - Slope SR 19 (LF)	8" - Slope SR 17 (LF)	10" - Slope SR 19 (LF)	8" Cured-in Place Pipe (LF)	10" Cured-in Place Pipe (LF)	15" Cured-in Place Pipe (LF)	8" Pipeburst (LF)	10" Pipeburst (LF)	12" Pipeburst (LF)	15" Pipeburst (LF)	18" Pipeburst (LF)	8" Open Cut Only (LF)	10" Open Cut Only (LF)	12" Open Cut Only (LF)	15" Open Cut Only (LF)	18" Open Cut Only (LF)	21" Open Cut Only (LF)	Remove & Replace Concrete Pmt. (SF)	Remove & Replace Asphalt Pmt. (SF)	Remove & Replace Driveway SOWK. (SF)	Remove & Replace Concrete Curb (LF)	Sodding (SF)	Rehab Services (EA)	Television Pre Inspection
2017	59	045-0432	9.3	045-0451	8.2	8	VCP	210								210																						4	210	

ATLAS 59 - MANHOLE REHAB SCHEDULE

Atlas	Basin	MH	Diameter (ft)	Depth (ft) (Rim to Invert)	Grade to Rim	Drop Manhole	Address	Surface Type	TYPE A (EA)	TYPE B (EA)	TYPE C (EA)	TYPE D (EA)	TYPE E (EA)	TYPE Gg (SF)	TYPE Gh (EA)	TYPE Gk (EA MH)	TYPE Go (EA MH)	TYPE Gp (EA)	TYPE Gr (EA MH)	TYPE Gs (SF)	MANHOLE REPLACEMENT 4" I.D. (EA)	Additional Depth OVER 6" FOR 4" I.D. (VF)	DROP MANHOLE REPLACEMENT 4" I.D. (EA)	Additional Depth OVER 6" FOR 4" I.D. DROP (VF)	MANHOLE REPLACEMENT 5" I.D. (EA)	Additional Depth OVER 6" FOR 5" I.D. (VF)	DROP MANHOLE REPLACEMENT 5" I.D. (EA)	Additional Depth OVER 6" FOR 5" I.D. DROP (VF)	LAMPHOLE REPLACEMENT (EA)	REPLACE LAMPHOLE FRAME AND COVER (EA)	SEALED LID REPLACEMENT (EA)	MANHOLE STRIP REMOVAL AND REPAIR (PER MH)			
59		045-0417	4	13.24	0	No	2409 E 31st St	Concrete Collar								1																			
59		045-0418	4	6.88	0	No	2408 E 30th St	Grass/Dirt		1																									
59		045-0420	4	14.31	0	No	2511 E 31st St	Grass/Dirt								1																			
59		045-0421	4	15.19	0	No	2521 E 31st St	Grass/Dirt	1							1																			
59		045-0423	4	5.61	0	No	2505 E 31st St	Concrete Pavement		1																									
59		045-0426	4	3.57	0	No	2629 E 31st St	Concrete Pavement				1																							
59		045-0427	4	4.05	0	No	2691 E 31st St	Concrete Pavement					1																						
59		045-0428	4	4.47	0	No	3041 S Birmingham Pl	Concrete Pavement		1			1																						
59		045-0429	4	5.35	0	No	2407 E 30th St	Concrete Pavement				1																							
59		045-0430	4	9.22	0	No	2404 E 29th St	Concrete Pavement					1			1																			
59		045-0431	4	8.23	0	No	2415 E 30th St	Grass/Dirt								1																			

REHABILITATION METHODS

- TYPE A
REPLACEMENT OF MANHOLE COVER, FRAME AND FRAME SEAL (418)

TYPE B
REPLACEMENT OF MANHOLE FRAME SEAL (418)

TYPE C
REPLACEMENT OF MANHOLE COVER, FRAME, FRAME SEAL AND CHIMNEY (418)

TYPE D
REPLACEMENT OF MANHOLE FRAME SEAL AND CHIMNEY (418)

TYPE E
PRECAST CORBEL SECTION (418)

TYPE Gg
INTERIOR MANHOLE WALL REHABILITATION (421)

TYPE Gh
BENCH AND INVERT REHABILITATION (419)

TYPE Gk
PIPE SEAL REHABILITATION (421)

TYPE Go
PLUG LIFT HOLES, PLUG HOLES (419)
- TYPE Gp
SEAL PRE-CAST JOINTS (421)

TYPE Gc
PATCH HOLE (419)

TYPE Gs
EPOXY COATING (421)

TYPE L
REPLACEMENT OF MANHOLE STEPS – AT THE TIME OF MANHOLE REHABILITATION, MANHOLE STEPS SHALL BE EVALUATED AND REPLACED ON A PER-MANHOLE BASIS, AND INCLUDE ALL THE STEPS IN THE MANHOLE REGARDLESS OF SIZE OR HEIGHT OF THE MANHOLE. (420)

TYPE I
CLEAN MANHOLE (Spec'd)

MANHOLE REPLACEMENT

COMPLETE MANHOLE REPLACEMENT (416)

MANHOLE REPLACEMENT

ADDITIONAL FOOTAGE (416)

LAMPHOLE REPLACEMENT

LAMPHOLE REPLACEMENT (417)

REGISTERED PROFESSIONAL ENGINEER
OKLAHOMA
10/13/16
MITTASCH
21102

ATLAS 59 - LINE and MANHOLE SCHEDULE
TULUA PROJECT NO. ES 2024-04
CROW CREEK
SPECIFIC REMEDIATION PLAN, CONTRACT 5
CITY OF TULSA, OKLAHOMA
WATER AND SEWER DEPARTMENT
PLANS AND ESTIMATES PREPARED BY:
TETRA TECH
TRADE & ROAD Steel, Suite 301, Tulsa, OK 74133
TEL 918.248.5585

REVISION

BY

DATE

PLAN SCALE

DESIGNED

T1

01/2025

SURVEY

T1

01/2025

PROJ MGR

SW

09/25

LEAD ENGR

SW

09/25

FIELD MGR

SW

10/15

FILE

DRAWING

DATE

OCTOBER 2025



APPROVED

DESIGN MANAGER

DATE

OCTOBER 2025

15 OF 44 SHEETS



APPROXIMATE LOCATION EXISTING SERVICE TAP.
CONTRACTOR TO VERIFY LOCATIONS THROUGH
PRECONSTRUCTION CCTV DATA

NOTE:
FOR LINE WORK IN PAVED AREAS, PAVEMENT AND
TRENCHING TO BE COMPLETED PER CITY OF TULSA
STD. 713.

GAS LINE LOCATIONS SHOWN ARE FROM OKLAHOMA
NATURAL GAS ATLAS AND ARE APPROXIMATE

REGISTERED PROFESSIONAL ENGINEER
OKLAHOMA
21102
DAVID MITTSCH
10/8/15

BEFORE YOU BIG
CALL OKIE

ATLAS 59 - DETAILS

TMUA PROJECT NO. ES 2024-04

CROW CREEK

SPECIFIC REMEDIATION PLAN, CONTRACT 5

CITY OF TULSA, OKLAHOMA

WATER AND SEWER DEPARTMENT

PLANS AND ESTIMATES PREPARED BY:

TETRA TECH

7545 E. 63rd Street, Suite 301, Tulsa, OK 74133

TEL 918.246.3009

7545 E. 63rd Street, Suite 301, Tulsa, OK 74133

TEL 918.246.3009

REVISION

BY

DATE

PLAN SCALE

DRAWN

TI

01/2/2025

APPROVED

PROJECT SCALE

DESIGNED

TI

01/2/2025

PROJ. MGR

9/1/2025

LEAD ENGR

9/1/2025

FIELD MGR

9/1/2025

DRAWING

9/1/2025

FILE

ATLAS PAGE NO. 59

DATE



OCTOBER 2025

SHEET

16 OF 44 SHEETS

DESIGN MANAGER

Shawn D. M...



ATLAS 60 - LINE REHAB SCHEDULE

[illegible]

ATLAS 80 - LINE SCHEDULE					
TMUA PROJECT NO. ES 2024-04					
CROW CREEK					
CITY OF TULSA, OKLAHOMA					
WATER AND SEWER DEPARTMENT					
PLANS AND ESTIMATES PREPARED BY:					
 TETRA TECH 7404 E. 83rd Street, Suite 301, Tulsa, OK 74133 TEL:918.248.3889					
REVISION	BY	DATE	PLAN SCALE:	DRAWN	
				TI	01/2026
				DESIGNED	TI
				SURVEY	01/2026
				PROJ MGR.	SV
					10/25
				LEAD ENGR.	EJK 085
				FIELD MGR.	Brent 10/25
FUE				DRAWING	
ATLAS PAGE NO.	80				
			APPROVED:		
			DATE:	OCTOBER 2025	
			SHEET 18 OF 44 SHEETS		
			DESIGN MANAGER: <i>[Signature]</i>		

ATLAS 60 - MANHOLE SCHEDULE - 2

Atlas	Basin	MHI	Diameter (in)	Depth (ft) (Rim to Invert)	Grade to Rim	Drop Manhole	Address	Surface Type	TYPE A (EA)	TYPE B (EA)	TYPE C (EA)	TYPE D (EA)	TYPE E (EA)	TYPE F (SF)	TYPE G (EA)	TYPE G1 (EA MH)	TYPE G2 (EA MH)	TYPE G3 (EA)	TYPE G4 (EA MH)	TYPE G5 (SF)	MANHOLE REPLACEMENT 4' OVER 6' (EA)	Additional Depth OVER 6' FOR 4' (LF)	DROP MANHOLE REPLACEMENT 4' I.D. (EA)	Additional Depth OVER 6' FOR 4' (LF)	MANHOLE REPLACEMENT 5' I.D. (EA)	Additional Depth OVER 6' FOR 5' (LF)	DROP MANHOLE REPLACEMENT 5' I.D. (EA)	Additional Depth OVER 6' FOR 5' (LF)	LAMPHOLE REPLACEMENT (EA)	REPLACE LAMPHOLE FRAME AND COVER (EA)	SEALED I.D. (EA)	MANHOLE STOP REMOVAL AND REPLACEMENT, TYPE (PER MH)	
60	45	045-0356	4	6.33	0	No	3001 S Wheeling Ave	Concrete Pavement		1																							
60	45	045-0357	4	5	0	No	1906 E 30th St	Grass/Dirt													1												
60	45	045-0358	4	5.55	0	No	1817 E 30th St	Grass/Dirt													1												
60	45	045-0359	4	7.38	0	No	2936 S Yorktown Ave	Grass/Dirt													1												
60	45	045-0362	4	11.89	0	No	2109 E 30th Pl	Grass/Dirt		1												1.4											
60	45	045-0363	4	8.83	0.5	No	2126 E 30th St	Grass/Dirt																									
60	45	045-0365	4	5.42	0	No	2121 E 30th St	Grass/Dirt																									
60	45	045-0366	4	7.9	0	No	2141 E 30th St	Grass/Dirt																									
60	45	045-0367	4	7.14	0	No	2141 E 30th St	Grass/Dirt																									
60	45	045-0369	4	5.94	0	No	2121 E 30th St	Grass/Dirt																									
60	45	045-0403	4	9.05	0	Yes	3091 S Zions Ave	Concrete Collar																									
60	45	045-0404	4	14.24	1.9	Yes	2151 E 31st St	Grass/Dirt																									
60	45	045-0405	4	11.66	0	No	2131 E 31st St	Grass/Dirt																									
60	45	045-0406	4	12.05	0	No	3049 S Yorktown Ave	Grass/Dirt																									
60	45	045-0407	4	5.7	0	No	2222 E 30th Pl	Grass/Dirt																									
60	45	045-0408	4	8.10	0	No	2222 E 30th Pl	Grass/Dirt																									
60	45	045-0409	4	10.51	0	Yes	2215 E 30th Pl	Grass/Dirt																									
60	45	045-0411	4	7	0	No	2242 E 31st St	Grass/Dirt																									
60	45	045-0412	4	8.4	0	No	2252 E 31st St	Grass/Dirt																									
60	45	045-0413	4	9.03	0	No	2240 E 31st St	Grass/Dirt		1																							
60	45	045-0414	4	6.28	0.14	No	2242 E 30th Pl	Grass/Dirt																									
60	45	045-0416	4	10.63	0.3	No	2375 E 31st St	Grass/Dirt																									
60	45	045-0558	4	10.1	-0.16	No	1550 E 29th St	Grass/Dirt																									
60	45	045-0559	5	13.9	0	No	1606 E 28th St	Grass/Dirt																									1
60	45	045-0576	4	6.54	0	No	2733 S Ulicia Ave	Grass/Dirt																									1
60	45	045-0580	4	6.5	0	No	2701 S Victor Ave	Grass/Dirt																									
60	45	045-0581	4	6.49	0	No	2701 S Victor Ave	Grass/Dirt																									
60	45	045-0582	4	7.04	0.2	No	1886 E 27th St	Grass/Dirt																									
60	45	045-0586	4	6.26	0	No	2845 S Victor Ave	Concrete Pavement																									
60	45	045-0587	4	7.25	0	No	2847 S Victor Ave	Grass/Dirt																									
60	45	045-0589	4	5.23	0	No	2801 S Victor Ave	Grass/Dirt																									
60	45	045-0723	4	8.82	0	Yes	1345 E 29th St	Grass/Dirt																									
60	45	045-0724	4	0.667	4.70	No	1329 E 29th St	Grass/Dirt																									
60	45	045-0732	4	5.45	0	No	3031 S Rockford Rd	Asphalt																									
60	45	045-0757	4	5.9	0	No	2222 E 30th Pl	Grass/Dirt																									1
60	45	045-0767	4	12.1	0	No	2707 S Rockford Rd	Grass/Dirt																									1
60	45	045-0775	4	8.87	0.3	Yes	2687 S Ulicia Ave	Grass/Dirt																									1
60	45	045-0788	4	6.9	0.15	No	3007 S Rockford Rd	Grass/Dirt																									1
60	45	045-0791	4	4.32	0.2	No	3015 S Rockford Rd	Other																									1
60	45	045-0792	4	8.48	0	Yes	3015 S Rockford Rd	Grass/Dirt																									1
60	45	045-0795	4	16.19	0	No	3020 S Trenton Ave	Grass/Dirt																									1
60	45	045-0796	4	14.15	0	No	3020 S Trenton Ave	Grass/Dirt																									1
60	62	062-0934	4	11.06	1.82	No	1881 E 27th St	Grass/Dirt																									1
60	62	062-0935	4	11.87	0	No	1881 E 27th St	Grass/Dirt																									1
60	62	062-0936	4	11.51	0	No	1881 E 27th St	Grass/Dirt																									1

REHABILITATION METHODS

TYPE A
REPLACEMENT OF MANHOLE COVER, FRAME AND
FRAME SEAL (418)

TYPE B

REPLACEMENT OF MANHOLE FRAME SEAL (418)

TYPE C
REPLACEMENT OF MANHOLE COVER, FRAME, FRAME
SEAL AND CHIMNEY (418)

TYPE D
REPLACEMENT OF MANHOLE FRAME SEAL AND CHIMNEY
(418)

TYPE Ic
PRECAST CORBEL SECTION (418)

TYPE Gg
INTERIOR MANHOLE WALL REHABILITATION (421)

TYPE Gh

TYPE GK

PIPE SEAL REHABILITATION (421)

TYPE GO
PLUG LIFT HOLES, PLUG HOLES (419)

TYPE Gr
SEAL PRE-CAST JOINTS (421)

TYPE Gr
PATCH HOLE (419)

TYPE Gs
EPOXY COATING (421)

TYPE 1. REPLACEMENT OF MANHOLE STEPS - AT THE TIME OF MANHOLE REHABILITATION, MANHOLE STEPS SHALL BE EVALUATED AND REPLACED ON A PER-MANHOLE BASIS, AND INCLUDE ALL THE STEPS IN THE MANHOLE REARFOOT OF SIZE OR HEIGHT OF THE MANHOLE. (420)

TYPE I
CLEAN MANHOLE (Special)
MANHOLE REPLACEMENT
COMPLETE MANHOLE REPLACEMENT (416)
MANHOLE REPLACEMENT
ADDITIONAL FOOTAGE (416)
LAMPPOLE REPLACEMENT
LAMPPOLE REPLACEMENT (417)




16.4* (Italicised) - DENOTES MANHOLE DEPTH FROM CITY OF TULSA ATLAS

CONTRACTOR SHALL NOT STOCKPILE MATERIAL OR
STORE ANY EQUIPMENT OVERNIGHT IN THE TULSA
REGULATORY FLOODPLAIN



TETRA TECH
7645 E. 63rd Street, Suite 301, Tulsa, OK 74133
TEL918.249.3909

REVISION	BY	DATE	PLAN SCALE	DRAWN	TI	01/2026	APPROVED:
				DESIGNED	TI	01/2026	
				SURVEY	TI	01/2026	
				PROJ. MGR.	8/	09/25	
			PROFILE SCALE: HORIZONTAL	LEAD ENGR.	62/	10/5	
			VERTICAL	FIELD MGR.	12/10/5		
			FILE	DRAWING:			
			ATLAS PAGE NO.	60			
			SHEET 20 OF 44 SHEETS				




APPROXIMATE LOCATION EXISTING SERVICE TAP,
CONTRACTOR TO VERIFY LOCATIONS THROUGH
PRECONSTRUCTION CCTV DATA

NOTE:
FOR LINE WORK IN PAVED AREAS, PAVEMENT AND
TRENCHING TO BE COMPLETED PER CITY OF TULSA
STD. 713.

GAS LINE LOCATIONS SHOWN ARE FROM OKLAHOMA
NATURAL GAS ATLAS AND ARE APPROXIMATE




ATLAS 60 - DETAILS - 1	
TMUA PROJECT NO. ES 2024-04	
CROW CREEK	
SPECIFIC REMEDIATION PLAN, CONTRACT 5	
CITY OF TULSA, OKLAHOMA	
WATER AND SEWER DEPARTMENT	
PLANS AND ESTIMATES PREPARED BY:	
TETRA TECH	
7845 E. 69th Street, Suite 301, Tulsa, OK 74133	
TEL 918.248.3809	
DESIGNED BY: TI	
DATE: 10/1/2024	
CHECKED BY: TI	
DATE: 10/1/2024	
DRAWN BY: TI	
DATE: 10/1/2024	
PROJECT NO. 19-123	
LEAD ENGR. 10/1/25	
DESIGN MANAGER 10/1/25	
DATE: OCTOBER 2025	
SHEET 21 OF 44 SHEETS	





045-0239 - 045-0238
OPEN CUT

045-0238 - 045-0558
PIPE BURST EXISTING 21 INCH
WITH 24 INCH



045-0329 - 045-0328
POINT REPAIR



045-0238 - 045-0558
PIPE BURST

045-0239 - 045-0238
OPEN CUT

APPROXIMATE LOCATION EXISTING SERVICE TAP.
CONTRACTOR TO VERIFY LOCATIONS THROUGH
PRECONSTRUCTION CCTV DATA

NOTE:
FOR LINE WORK IN PAVED AREAS, PAVEMENT AND
TRENCHING TO BE COMPLETED PER CITY OF TULSA
STD. 713.

GAS LINE LOCATIONS SHOWN ARE FROM OKLAHOMA
NATURAL GAS ATLAS AND ARE APPROXIMATE

REGISTERED PROFESSIONAL ENGINEER
OKLAHOMA
21102
M. J. MITCHELL

BEFORE YOU SIGN
CALL OKIE

ATLAS 60 - DETAILS - 2

TMUA PROJECT NO. ES 2024-04

CROW CREEK

SPECIFIC REMEDIATION PLAN, CONTRACT 5

CITY OF TULSA, OKLAHOMA

WATER AND SEWER DEPARTMENT

PLANS AND ESTIMATES PREPARED BY:

TETRA TECH

7545 E. 63rd Street, Suite 301, Tulsa, OK 74133

TEL: 918.249.2009

REVISION	BY	DATE	PLAN SCALE	TH	TI	APPROVED
			DRAWN	TI	01/20/25	
			DESIGNED	TI	01/20/25	
			SURVEY	TI	01/20/25	
			PROJECT SCALE			
			HORIZONTAL			
			VERTICAL			
			FIELD WORK			
			DRAWING			
			FILE			
			ATLAS PAGE NO.	60		
			SHEET	22	OF	44 SHEETS

TH

TETRA TECH

7545 E. 63rd Street, Suite 301, Tulsa, OK 74133

TEL: 918.249.2009

APPROVED

TH

01/20/25

DESIGNED

TI

01/20/25

SURVEY

TI

01/20/25

PROJECT SCALE

HORIZONTAL

VERTICAL

FIELD WORK

DRAWING

FILE

ATLAS PAGE NO.


60

SHEET


22

OF

44 SHEETS




045-0050 - 045-0049
PIEBURST
SEE SHEET 25
FOR PROFILE



045-0061 - 045-0060
PIEBURST
SEE SHEET 25
FOR PROFILE

045-0062 - 045-0061
PIEBURST
SEE SHEET 25
FOR PROFILE



7645 E. 63rd Street, Suite 301, Tulsa, OK 74133
TEL 918.249.3909

PLANS AND ESTIMATES PREPARED BY:




WATER AND SEWER DEPARTMENT

CITY OF LOS ANGELES, CALIFORNIA

SPECIFIC REMEDIATION PLAN, CONTRACT 5

[illegible]











APPROXIMATE LOCATION EXISTING SERVICE TAP,
CONTRACTOR TO VERIFY LOCATIONS THROUGH
PRECONSTRUCTION CCTV DATA

NOTE:
FOR LINE WORK IN PAVED AREAS, PAVEMENT AND
TRENCHING TO BE COMPLETED PER CITY OF TULSA
STD. 713.

GAS LINE LOCATIONS SHOWN ARE FROM OKLAHOMA
NATURAL GAS ATLAS AND ARE APPROXIMATE

[illegible]







APPROXIMATE LOCATION EXISTING SERVICE TAP,
CONTRACTOR TO VERIFY LOCATIONS THROUGH
PRECONSTRUCTION CCTV DATA

NOTE:
FOR LINE WORK IN PAVED AREAS, PAVEMENT AND
TRENCHING TO BE COMPLETED PER CITY OF TULSA
STD. 713.

GAS LINE LOCATIONS SHOWN ARE FROM OKLAHOMA
NATURAL GAS ATLAS AND ARE APPROXIMATE

REGISTERED PROFESSIONAL ENGINEER 11/9/25 RYAN L. MITCHELL 2102 OKLAHOMA		ATLAS 60 - PROFILES - 2 TMUA PROJECT NO. ES 2024-04 CROW CREEK SPECIFIC REMEDIATION PLAN, CONTRACT 5 CITY OF TULSA, OKLAHOMA WATER AND SEWER DEPARTMENT	
PLANS AND ESTIMATES PREPARED BY: TETRA TECH 7645 E. 63rd Street, Suite 301, Tulsa, OK 74133 TEL: 918.248.3809		DRAWN: TI 01/2025 DESIGNED: TI 01/2025 SURVEY: TI 01/2025 PROJECT NO: 51 10/25 LEAD ENGR: 11/01/25 FIELD ENGR: 11/01/25 DATE: OCTOBER 2025 SHEET: 26 OF 44 SHEETS	
REGION: ST: DATE: APPROVED: [Signature]		FILE: DRAWING: 11/01/25	





ATLAS 60 - PROFILES - 3			
TMUA PROJECT NO. ES 2024-04			
CROW CREEK			
SPECIFIC REMEDIATION PLAN, CONTRACT 5			
CITY OF TULSA, OKLAHOMA			
WATER AND SEWER DEPARTMENT			
PLANS AND ESTIMATES PREPARED BY:			


APPROXIMATE LOCATION EXISTING SERVICE TAP,
CONTRACTOR TO VERIFY LOCATIONS THROUGH
PRECONSTRUCTION CCTV DATA

NOTE:
FOR LINE WORK IN PAVED AREAS, PAVEMENT AND
TRENCHING TO BE COMPLETED PER CITY OF TULSA
STD. 713.

GAS LINE LOCATIONS SHOWN ARE FROM OKLAHOMA
NATURAL GAS ATLAS AND ARE APPROXIMATE

REVISION	BY	DATE	PLAN SCALE	DRAWN	TT	APPROVED
				DESIGNED	TT	10/2/25
				SURVEY	TT	10/2/25
				FIELD ENGR.	CK 10/25	
				LEAD ENGR.	CK 10/25	
				FIELD ENGR.	CK 10/25	
				FILE		
				ATLAS PAGE NO.	60	
				SHEET	27 OF 44 SHEETS	

SEE ATLAS 60
31st ST



SEE ATLAS 96
S. Peoria Ave.

S. Lewis Ave.
SEE ATLAS 94

36th ST.
SEE ATLAS 138

LEGEND

MANHOLE/LAMPPOLE REPLACEMENT

TOPSIDE MANHOLE/LAMPPOLE REPAIR

INTERIOR MANHOLE REPAIR

APPROXIMATE LOCATION
OF TULSA REGULATORY
FLOODPLAIN

MANHOLE BUBBLE

MANHOLE #
MANHOLE DEPTH (per atlas)



POINT REPAIR

LINE REPLACEMENT
OPEN CUT OR PIPEBURST

SLIPLINE OR CIPP

COULD NOT LOCATE or ACCESS
RECOMMENDATION TO BE MADE
DURING CONSTRUCTION

CNL



CONTRACTOR SHALL NOT STOCKPILE MATERIAL OR
STORE ANY EQUIPMENT OVERNIGHT IN THE TULSA
REGULATORY FLOODPLAIN



TETRA TECH
1744 E. 30th Street, Suite 301, Tulsa, OK 74133
TEL 918.246.5989

PLANS AND ESTIMATES PREPARED BY:

CITY OF TULSA, OKLAHOMA
WATER AND SEWER DEPARTMENT

ATLAS 95
TULSA PROJECT NO. ES 2024-04
CROW CREEK
SPECIFIC REMEDIATION PLAN, CONTRACT 5

REVISION		BY	DATE	PLAN SCALE	TH
				DESIGNED	TI
				SURVEY	TI
				PROJECT SCALE	50' / 10' / 5'
				HORIZONTAL	50' / 10' / 5'
				VERTICAL	50' / 10' / 5'
				FILE	
				ATLAS PAGE NO.	95
				APPROVED	
				DATE	OCTOBER 2025
				SHEET	28 OF 44 SHEETS

ATLAS 95 - LINE REHAB SCHEDULE

[illegible][illegible]

REHABILITATION METHODS

TYPE 1
REPLACEMENT OF MANHOLE STEPS - AT THE TIME OF MANHOLE REHABILITATION, MANHOLE STEPS SHALL BE EVALUATED AND REPLACED ON A PER-MANHOLE BASIS, AND INCLUDE ALL THE STEPS IN THE MANHOLE REGARDLESS OF SIZE OR HEIGHT OF THE MANHOLE. (420)

TYPE 1
CLEAN MANHOLE (Specia)
MANHOLE REPLACEMENT
COMPLETE MANHOLE REPLACEMENT (416)
MANHOLE REPLACEMENT
ADDITIONAL FOOTAGE (416)
LAMPHOLE REPLACEMENT (417)
LAMPHOLE REPLACEMENT (417)

WATER AND SEWER DEPARTMENT

PLANS AND ESTIMATES PREPARED BY:


TETRA TECH

7645 E. 53rd Street, Suite 301, Tulsa, OK 74133
TEL: 918.248.3009
FAX: 918.248.3090





045-0458 045-0457
OPEN CUT
SEE SHEET 32 FOR
PROFILE

045-0466 045-0458
PIPE BURST
SEE SHEET 32 FOR
PROFILE



045-0390-045-0389
PIPE BURST
SEE SHEET 32 FOR
PROFILE





ATLAS 95 - DETAILS
TMUA PROJECT NO. ES 2024-04
CROW CREEK
SPECIFIC REMEDIATION PLAN, CONTRACT 5
CITY OF TULSA, OKLAHOMA
WATER AND SEWER DEPARTMENT
PLANS AND ESTIMATES PREPARED BY:
TETRA TECH
7645 E. 62nd Street, Suite 301, Tulsa, OK 74133
TEL 918.246.3565

APPROXIMATE LOCATION EXISTING SERVICE TAP,
CONTRACTOR TO VERIFY LOCATIONS THROUGH
PRECONSTRUCTION CCTV DATA

NOTE:
FOR LINE WORK IN PAVED AREAS, PAVEMENT AND
TRENCHING TO BE COMPLETED PER CITY OF TULSA
STD. 713.

GAS LINE LOCATIONS SHOWN ARE FROM OKLAHOMA
NATURAL GAS ATLAS AND ARE APPROXIMATE

REVISION	BY	DATE	PLAN SCALE		APPROVED
			DRAWN	TI	01/2024
			DESIGNED	TI	01/2024
			SURVEY	TI	01/2024
			PROJ. MGR.	SV	10/25
			LEAD ENGR.	10/25	
			FIELD MGR.	10/25	
			FILE	DRAWING	DATE: OCTOBER 2025
			ATLAS PAGE NO.	60	SHEET 31 OF 44 SHEETS



APPROXIMATE LOCATION EXISTING SERVICE TAP,
CONTRACTOR TO VERIFY LOCATIONS THROUGH
PRECONSTRUCTION CCTV DATA


NOTE:
FOR LINE WORK IN PAVED AREAS, PAVEMENT AND
TRENCHING TO BE COMPLETED PER CITY OF TULSA
STD. 713.

GAS LINE LOCATIONS SHOWN ARE FROM OKLAHOMA
NATURAL GAS ATLAS AND ARE APPROXIMATE

7/1 05

FILE NO. 249-3490

REVISION	BY	DATE	PLAN SCALE:	DATE	APPROVED:
			BROWN	10/2/2025	
			DESIGNED	11/10/2025	
			SURVEY	11/10/2025	
			TR	10/2/2025	
			PROJ. MGR	10/2/25	
			LEAD ENGR	10/2/25	
			FIELD MGR	10/2/25	
			VERTICAL	10/2/25	
			DRAWING	10/2/25	
			FILE:		
			ATLAS PAGE NO.:	95	
			DATE:	OCTOBER 2025	
			SHEET 32 OF 44 SHEETS		



- LEGEND**
- MANHOLE/LAMPPOLE REPLACEMENT
- TOPSIDE MANHOLE/LAMPPOLE REPAIR
- INTERIOR MANHOLE REPAIR
- APPROXIMATE LOCATION OF TULSA REGULATORY FLOODPLAIN
- MANHOLE BUBBLE
- MANHOLE #
- MANHOLE DEPTH (per atlas)

- POINT REPAIR
- LINE REPLACEMENT
OPEN CUT OR PIPEBURST
- SUPLINE OR CIPP
- COULD NOT LOCATE or ACCESS
RECOMMENDATION TO BE MADE
DURING CONSTRUCTION
- CNL
- NOTE:
REFER TO LINE REHAB SCHEDULE TO DETERMINE IF LINE
REHAB IS OPEN CUT OR PIPEBURST, SUPLINE OR CIPP.

SEE ATLAS 33

21st ST



26th ST

SEE ATLAS 15

S. Peoria Ave.

15th ST

SEE ATLAS 3



TETRA TECH
7645 E. 63rd Street, Suite 301, Tulsa, OK 74133
TEL 918.248.3909

ATLAS 14 - ADD ALTERNATE 1	
TULSA PROJECT NO. ES 2024-04	
CROW CREEK	
SPECIFIC REMEDIATION PLAN, CONTRACT 5	
WATER AND SEWER DEPARTMENT	
PLANS AND ESTIMATES PREPARED BY:	
TETRA TECH	
7645 E. 63rd Street, Suite 301, Tulsa, OK 74133	
TEL 918.248.3909	
REVISION	
BY	DATE
DESIGNED	11/1/2023
SURVEY	11/1/2023
PROJECT SCALE	1" = 100'
FIELD ENGR.	11/1/2023
FILE	11/1/2023
DATE	OCTOBER 2025
SHEET 33 OF 44 SHEETS	



CONTRACTOR SHALL NOT STOCKPILE MATERIAL OR
STORE ANY EQUIPMENT OVERNIGHT IN THE TULSA
REGULATORY FLOODPLAIN

ATLAS 14 - ADD ALTERNATE 1 - LINE REHAB SCHEDULE

[illegible]

SEGMENT 044-0208 TO 044-0536 TO BE RE-TYPED DURING CONSTRUCTION AND PROVIDED TO ENGINEER FOR REHAB CONFIRMATION DUE TO INCOMPLETE DATA. ESTIMATED 8" OPEN CUT FOR REHAB.

ATLAS 14 - ADD ALTERNATE 1 - LINE SCHEDULE							
TMUA PROJECT NO. ES 2024-04							
CROW CREEK SPECIFIC REMEDIATION PLAN, CONTRACT 5							
CITY OF TULSA, WATER AND SEWER DEPARTMENT							
PLANS AND ESTIMATES PREPARED BY:							
 TETRA TECH 7646 E. 93rd Street, Suite 301, Tulsa, OK 74133 TEL:918.489.3869							
REVISION	BY	DATE	PLAN SCALE:	DRAWN	TI	01/22/25	APPROVED:
				DESIGNED	TT	01/22/25	
				SURVEY	TT	01/22/25	
				PROJECT SCALE:			
				HORIZONTAL			
				VERTICAL			
				FIELD MGR.	SW	11/15/25	
				LEAD ENGR.	KJ	11/15/25	
				FIELD MGR.	SPRUE	12/15/25	
				DRAWING			
				FILE			
				ATLAS PAGE NO.	14		
DATE: OCTOBER 2025 SHEET 34 OF 44 SHEETS <i>Chen g. m</i> REGION MANAGER							




044-0199 - 044-0198
PIPE BURST
SEE SHEET 37 FOR
PROFILE

044-0194 - 044-0193
CIPP






044-0536 - 044-0206
POINT REPAIR

044-0208 - 044-0536
OPEN CUT
SEE SHEET 37 FOR
PROFILE

REVISION	BY	DATE	PLAN SCALE	DRAWN	TI	01/22/26	APPROVED:
				DESIGNED	TI	01/22/26	
				SURVEY	TI	01/22/26	
				PROFILE SCALE:			
				HORIZONTAL			
				PROJ. MGR.	SV	10/15	
				LEAD ENGR.	DK	10/15	
				VERTICAL			
				FIELD MGR.	JRM	10/15	
				DRAWING:			
				ATLAS PAGE NO.	14		
				DATE:			
				OCTOBER 2025			
				SHEET 36 OF 44 SHEETS			



A north arrow pointing towards the top of the page, with the letter 'N' inside a circle. Below the arrow is a graphic scale bar with markings at 0, 20', 40', and 80'. To the left of the scale bar, the text 'SCALE: 1" = 40'' is written vertically.



APPROXIMATE LOCATION EXISTING SERVICE TAP
CONTRACTOR TO VERIFY LOCATIONS THROUGH
PRECONSTRUCTION CCTV DATA

NOTE:
FOR LINE WORK IN PAVED AREAS, PAVEMENT AND
TRENCHING TO BE COMPLETED PER CITY OF TULSA
STD. 713.

GAS LINE LOCATIONS SHOWN ARE FROM OKLAHOMA
NATURAL GAS ATLAS AND ARE APPROXIMATE

ATLAS 14 - ADD ALTERNATE 1 - PROFILES

TMUA PROJECT NO. ES 2024-04

SPECIFIC REMEDIATION PLAN, CONTRACT 5

WATER AND SEWER DEPARTMENT

ESTIMATES PREPARED BY:

BY: _____

LEIWA TECH

7645 E. 63rd Street, Suite 301, Tulsa, OK 74133
TEL: 918.249.3909

uite 301, Tulsa, OK 74133

U

DRAWN	TI	01/2022
-------	----	---------

DESIGNED	Tn	01/2022
----------	----	---------

SURVEY	Tt	01/2022
--------	----	---------

E:	PROJ. MGB.	8V	10/20
----	------------	----	-------

HEAD END	10/1
----------	------


DATE	10/10/10
BY	AK

FIELD MGR.	1/22/20	10/2/20
------------	---------	---------

DRAWING:

14

SEE ATLAS 34
S. Peoria Ave.



SEE ATLAS 14
21st ST

S. Lewis Ave.
SEE ATLAS 32

LEGEND

MANHOLE/LAMPHOLE REPLACEMENT

TOPSIDE MANHOLE/LAMPHOLE REPAIR

INTERIOR MANHOLE REPAIR

APPROXIMATE LOCATION
OF TULSA REGULATORY
FLOODPLAIN

MANHOLE BUBBLE

MANHOLE # 78
MANHOLE DEPTH (per atlas) 12.5

POINT REPAIR

**LINE REPLACEMENT
OPEN CUT OR PIPEBURST**

SLIPLINE OR CIPF


COULD NOT LOCATE or ACCESS.

DURING CONSTRUCTION

NOTE:
REFER TO LINE REHAB SCHEDULE TO DETERMINE IF LINE
REHAB IS OPEN CUT OR PIPEBURST, SLIPLINE OR CIPP.

26th PL

SEE ATLAS 60



CONTRACTOR SHALL NOT STOCKPILE MATERIAL OR
STORE ANY EQUIPMENT OVERNIGHT IN THE TULSA
REGULATORY FLOODPLAIN



PLANS AND ESTIMATES PREPARED BY

CITY OF TULSA, OKLAHOMA
WATER AND SEWER DEPARTMENT





ATLAS 33 - ADD ALTERNATE 2
TMUA PROJECT NO. ES 2024-04
CROW CREEK

	REVISION	BY	DATE	PLAN SCALE:	DRAWN	T ₁	T ₂ /T ₃	APPROVED:
					DESIGNED	T ₁	01/2026	
					SURVEY	T ₁	01/2026	
				PROFILE SCALE HORIZONTAL	PLOI MOR.	NV	1975	
				VERTICAL	LEAD ENOR.	W/S	185	
				FIELD MOR.	FIELD MOR.	174K	1D/b	
				FILE AS PAGE NO.: 33	DRAWING:			
					DATE:	OCTOBER 2025		
					SHEET 38 OF 44 SHEETS			

ATLAS 33-ADD ALTERNATE 2 - LINE SCHEDULE

[illegible]

ATLAS 33 - ADD ALTERNATE 2 - LINE SCHEDULE			
TMUA PROJECT NO. ES 2024-04			
CROW CREEK			
SPECIAL REMEDIATION PLAN CONTRACT 5			
CITY OF TULSA, OKLAHOMA			
WATER AND SEWER DEPARTMENT			
PLANS AND ESTIMATES PREPARED BY:			
 TETRA TECH 7504 E. 34th Street, Suite 301, Tulsa, OK 74133 TEL:318.249.5805			
REVISION	BY	DATE	PLAN SCALE:
			DRAWN
			DESIGNED
			SURVEY
			PROJ. MGR.
			FIELD MGR.
			VERTICAL
			FILE
			DRAWING
			ATLAS PAGE NO. 33
			APPROVED
			DATE
			SHEET 38 OF 44 SHEETS
			DESIGNED
			DATE
			OCTOBER 2025



045-0042 - 045-0041
2 POINT REPAIRS

044-0254 - 044-0253
OPEN CUT
SEE SHEET 43 FOR
PROFILE

NOTE:
FOR LINE WORK IN PAVED AREAS, PAVEMENT AND
TRENCHING TO BE COMPLETED PER CITY OF TULSA
STD. 713.

REVISION	BY	DATE	PLAN SCALE	DRAWN	TI	07/2023	APPROVED
				DESIGNED	T1	01/2023	
				SURVEY	T1	07/2023	
				PROFILE SCALE	SV	10/25	
				HORIZONTAL			
				VERTICAL			
				FIELD MARK			
			FILE	DRAWING			
			A7L&S PAGE NO.	33			

Shaw 5.07g

DESIGN MANAGER



DATE: OCTOBER 2025

SHEET 40 OF 44 SHEETS



ATLAS 33 - ADD ALTERNATE 2 - DETAILS 1
TMUA PROJECT NO. ES 2024-04
CROW CREEK SPECIFIC REMEDIATION PLAN, CONTRACT
CITY OF TULSA, OKLAHOMA WATER AND SEWER DEPARTMENT
PLANS AND ESTIMATES PREPARED BY:

MANHOLE REHAB SHOWN IS A PART OF THE BASE BID




044-0234 - 044-0233
PIPE BURST
SEE SHEET 43 FOR
PROFILE


044-0243 - 044-0233
PIPE BURST
SEE SHEET 43 FOR
PROFILE

044-0244 - 044-0243
PIPE BURST
SEE SHEET 43 FOR
PROFILE


044-0245 - 044-0244
POINT REPAIR



044-0249 - 044-0248
CIPP





044-0246 - 044-0245
CIPP



044-0238 - 044-0237
PIPE BURST
SEE SHEET 44 FOR
PROFILE

044-0239 - 044-0238
PIPE BURST
SEE SHEET 44 FOR
PROFILE



MANHOLE REHAB SHOWN
IS A PART OF THE BASE BID




ATLAS 33 - ADD ALTERNATE 2 - DETAILS 2
TMUA PROJECT NO. ES 2024-04
CROW CREEK
SPECIFIC REMEDIATION PLAN, CONTRACT 5
CITY OF TULSA, OKLAHOMA
WATER AND SEWER DEPARTMENT
PLANS AND ESTIMATES PREPARED BY:
TETRA TECH
704 E 63rd Street, Suite 301, Tulsa, OK 74133
TEL: 918.255.2585


DESIGNED BY: **TI** DATE: 07/2023
APPROVED BY: **TI** DATE: 07/2023
PROJECT NO.: **TMUA** DATE: 07/2023
LEAD ENGR: **6/27/2023**
FIELD WORK: **6/27/2023**
DATE: OCTOBER 2023
DRAWING: **DESIGN MANAGER**
FILE: **ATLAS PAGE NO. 33**

APPROXIMATE LOCATION EXISTING SERVICE TAP.
CONTRACTOR TO VERIFY LOCATIONS THROUGH
PRECONSTRUCTION CCTV DATA


NOTE:
FOR LINE WORK IN PAVED AREAS, PAVEMENT AND
TRENCHING TO BE COMPLETED PER CITY OF TULSA
STD. 713.
GAS LINE LOCATIONS SHOWN ARE FROM OKLAHOMA
NATURAL GAS ATLAS AND ARE APPROXIMATE



044-0261 - 044-0260
PIPE BURST
SEE SHEET 44 FOR
PROFILE




044-0251 - 044-0250
POINT REPAIR



044-0595 - 044-0257
SLIPLINE

044-0257 - 044-0256
SLIPLINE



**MANHOLE REHAB SHOWN
IS A PART OF THE BASE BID**

ATLAS 33 - ADD ALTERNATE 2 - DETAILS 3

TMUA PROJECT NO. ES 2024-04

CROW CREEK

[illegible]

CITY OF IULSA, ONLANTOWIA






WALLEN UND OBERFLÄCHE DER ANTIMONI

PLANS AND ESTIMATES PREPARED BY:



7645 E. 63rd Street, Suite 301, Tulsa, OK 74133
TEL.918.249.3909

REVISION	BY	DATE	PLAN SCALE	DRAWN	TR	01/20/20	APPROVED:
				DESIGNED	TR	01/20/20	
				SURVEY	TR	01/20/20	
			PROFILE SCALE	PROJ. MGR.	SV	10/15/20	
			HORIZONTAL	LEAD ENGR.	SV	10/25/20	
			VERTICAL	FIELD MGR.	SV	10/15/20	
				DRAWING:			
				FILE NO.	33		
				DATE:	OCTOBER 2025		
				SHEET	42 OF 44 SHEETS		



APPROXIMATE LOCATION EXISTING SERVICE TAP,
CONTRACTOR TO VERIFY LOCATIONS THROUGH
PRECONSTRUCTION CCTV DATA

NOTE:
FOR LINE WORK IN PAVED AREAS, PAVEMENT AND
TRENCHING TO BE COMPLETED PER CITY OF TULSA
STD. 713.

GAS LINE LOCATIONS SHOWN ARE FROM OKLAHOMA
NATURAL GAS ATLAS AND ARE APPROXIMATE

REGISTERED PROFESSIONAL ENGINEER
10/15/05
RYAN L. MITTASCH
21702
OKLAHOMA



BEFORE YOU DIG
CALL 811
OKLAHOMA

ATLAS 33 - ADD ALTERNATE 2 - PROFILES 1
TMUA PROJECT NO. ES 2024-04
CROW CREEK
SPECIFIC REMEDIATION PLAN, CONTRACT 5
CITY OF TULSA, OKLAHOMA
WATER AND SEWER DEPARTMENT

PLANS AND ESTIMATES PREPARED BY:
TETRA TECH
7645 E. 60th Street, Suite 301, Tulsa, OK 74133
TEL: 918.248.3899

REVISION	BY	DATE	PLAN SCALE	DESIGNED	DATE	APPROVED
			PLAN	TI	10/20/25	
			SURVEY	TI	10/20/25	
			PROFILE SCALE	PROJ. MGR.	10/15/25	
			VERTICAL	LEAD ENGINEER	10/15/25	
			FIELD WORK	DESIGN MANAGER	10/15/25	
			FILE	DRAWING		
			ATLAS PAGE NO.	33		
			SHEET	43 OF 44 SHEETS		

DATE: OCTOBER 2025



APPROXIMATE LOCATION EXISTING SERVICE TAP
CONTRACTOR TO VERIFY LOCATIONS THROUGH
PRECONSTRUCTION CCTV DATA

FOR LINE WORK IN PAVED AREAS. PAVEMENT AND TRENCHING TO BE COMPLETED PER CITY OF TULSA STD. 713.

GAS LINE LOCATIONS SHOWN ARE FROM OKLAHOMA
NATURAL GAS ATLAS AND ARE APPROXIMATE

REVISION		BY	DATE	PLAN SCALE	DRAWN	TI	01/2025	APPROVED
					DESIGNED	TI	01/2025	
					SURVEY	TI	01/2025	
				PROFILE SCALE	PROJ MOR	SI	10/25	
				HORIZONTAL	LEAD ENGR	SI	10/25	
				VERTICAL	FIELD MOR	SI	10/25	
				DRAWING				
				ATTAS PAGE NO.	33			

DRAWN BY: *Thomas G. M*
 DATE: OCTOBER 2025
 SHEET 44 OF 44 SHEETS
 DESIGN WARRNER



7645 E. 63rd Street, Suite 301, Tulsa, OK 74133
TEL918.249.3909

PLANS AND ESTIMATES PREPARED BY:

WATER AND SEWER DEPARTMENT

CITY OF TULSA, OKLAHOMA

OF FOOD MEDICATION, ENVIRONMENTAL

CROW CREEK

TMUA PROJECT NO. ES 2024-04

ATLAS 33 - ADD ALTERNATE 2 - PROFILES 2

