



PUBLIC WORKS
Engineering

DATE: September 22, 2025

TO: PAUL ZACHARY,
PUBLIC WORKS DEPUTY
DIRECTOR

FROM: H. SOMDECERFF,
PUBLIC WORKS DESIGN
MANAGER


The Specification Review Committee recommends and asks the Public Works Deputy Director to approve the following:

1. Approve Modification to Division 319 – Encasement, Concrete.
Summary of change: Revised references to the Standard Details.

Please call Marqua Jimmerson at (918) 596-7355 If you have any questions.

Thank you,

APPROVED:


Paul Zachary Deputy Director


Date

Cc: Public Works Engineering Services Specification Review Committee

PART 319 – ENCASEMENT, CONCRETE

- 319.1 The work under this item shall include the installation of concrete encasement as shown on the Drawings or as directed by the Inspector, in accordance with the Standard Details. Care shall be taken to ensure that placing of encasement does not deflect the pipe from the proper grade and alignment.
- 319.2 Sanitary sewers shall be encased when the depth of cut from the original ground elevation to the flow line of the pipe is 4 feet or less. Concrete encasement necessitated by trench widths more than the standard width as shown on the Standard Details shall be placed as directed by the Inspector.
- 319.3 Payment: Payment for this item shall be made at the unit price bid per cubic yard of concrete placed as encasement. All concrete encasement required because of excessive trench width shall be placed at the expense of the Contractor. No payment will be made for concrete used as fill or in excess of the theoretical quantity computation based on the Standard Details.