




- | | | |
|---|------|-------------|
| CAST IRON BODY WITH
STAINLESS STEEL TRIM | CS | CIST |
| VALVE POSITION INDICATOR | XIOI | W/INDICATOR |
| EXTERNAL AND INTERNAL
EPOXY COATING | KC | STANDARD |
| STAINLESS STEEL SLEEVE STEM | KG | STANDARD |

11. CHAMFER EXPOSED CORNERS, EDGE AROUND OPENINGS IN TOP.
12. BEARING PADS HAVE NO REBAR.

13. VAULT ASSEMBLY SHALL INCLUDE ALL MATERIALS AND LABOR FOR AN INSTALLED AUTOMATED METEOR READING (AMR) DEVICE PER CONSTRUCTION SPECIFICATIONS DIVISION V, AMR DEVICE. SHALL INCLUDE MJJ ANTENNA PENETRATING THRU HATCH, MJJ POTTED REGISTER, REQUIRED CABLE, AND GEL-CAIP OF REQUIRED AMR INSTALLATION SHALL BE APPROVED AND TESTED BY ENGINEER OR ENGINEER'S DESIGNER.



[Signature]
 CITY ENGINEER
 8/10/22
 [Signature]
 DESIGN MANAGER

STD. 534